



NOV 15 2012

9th Floor, L & C Annex
401 Church Street
Nashville, TN 37243-1531
Telephone: (615) 532-0554
FAX: (615) 532-0614

NOT TO BE USED FOR TITLE V APPLICATIONS

PERMIT APPLICATION

DEC 10 2012

APC 20

PLEASE TYPE OR PRINT AND SUBMIT IN DUPLICATE FOR EACH EMISSION SOURCE. ATTACH APPROPRIATE SOURCE DESCRIPTION FORMS.

1. ORGANIZATION'S LEGAL NAME American Tower Corporation - East Sevierville		# 308917	/// FOR	APC COMPANY POINT NO. 78-0314-01
2. MAILING ADDRESS (ST/RD/P.O. BOX) P.O. Box 63604			/// APC	APC LOG/PERMIT NO. 966713
CITY Phoenix	STATE AZ	ZIP CODE 85082	PHONE WITH AREA CODE 602-284-0280	
3. PRINCIPAL TECHNICAL CONTACT Scot Sandefur			PHONE WITH AREA CODE 602-284-0280	
4. SITE ADDRESS (ST/RD/HWY) 122-County Garage Rd			COUNTY NAME Sevier	
CITY OR DISTANCE TO NEAREST TOWN Sevierville		ZIP CODE 37876	PHONE WITH AREA CODE 602-284-0280	
5. EMISSION SOURCE NO. (NUMBER WHICH UNIQUELY IDENTIFIES THIS SOURCE) E1		PERMIT RENEWAL YES () NO (X)		

6. BRIEF DESCRIPTION OF EMISSION SOURCE

Emergency Backup Power - Industrial generator set: 131 hp / 80 kw, with 300 gallon diesel fuel belly tank.

7. TYPE OF PERMIT REQUESTED

CONSTRUCTION (X)	STARTING DATE 12/12/12	COMPLETION DATE 12/19/12	LAST PERMIT NUMBER	EMISSION SOURCE REFERENCE NUMBER
OPERATING ()	DATE CONSTRUCTION STARTED	DATE COMPLETED	LAST PERMIT NUMBER	EMISSION SOURCE REFERENCE NUMBER
LOCATION TRANSFER ()	TRANSFER DATE		LAST PERMIT NUMBER	EMISSION SOURCE REFERENCE NUMBER

ADDRESS OF LAST LOCATION

8. DESCRIBE CHANGES THAT HAVE BEEN MADE TO THIS EQUIPMENT OR OPERATION SINCE THE LAST CONSTRUCTION OR OPERATING PERMIT APPLICATION.

9. SIGNATURE (APPLICATION MUST BE SIGNED BEFORE IT WILL BE PROCESSED) 		DATE 11/9/12
10. SIGNER'S NAME (TYPE OR PRINT) Scot Sandefur	TITLE Director EH&S	PHONE WITH AREA CODE 602-284-0280

DEC 10 2012

STATE OF TENNESSEE
DEPARTMENT OF ENVIRONMENT AND CONSERVATION
DIVISION OF AIR POLLUTION CONTROL



9th Floor, L & C Annex
401 Church Street
Nashville, TN 37243-1531
Telephone: (615) 532-0554
FAX: (615) 532-0614

NOT TO BE USED FOR TITLE V APPLICATIONS

PROCESS OR FUEL BURNING SOURCE DESCRIPTION

APC21(& 24)

PLEASE TYPE OR PRINT, SUBMIT IN DUPLICATE AND ATTACH TO THE PERMIT APPLICATION.

1. ORGANIZATION NAME		# 308917		/// FOR	APC COMPANY-POINT NO.
American Tower Corporation - East Sevierville					
2. EMISSION SOURCE NO. (AS ON PERMIT APPLICATION)		SIC CODE		/// APC	APC PERMIT/LOG NO.
E1					
3. DESCRIPTION OF PROCESS OR FUEL BURNING UNIT					
Emergency Backup Generator - Industrial Generator (diesel) set; 131 hp, 80kw, 300 gallon diesel belly tank.					
4. NORMAL OPERATION:	HOURS/DAY	DAYS/WEEK	WEEKS/YEAR	DAYS/YEAR	
→	Varies	Varies	Varies	Varies	
5. PERCENT ANNUAL THROUGHPUT:	DEC.-FEB.	MARCH-MAY	JUNE-AUG.	SEPT.-NOV.	
→	25 %	25 %	25 %	25 %	
6. TYPE OF PERMIT APPLICATION					(CHECK BELOW ONE ONLY)
PROCESS SOURCE: APPLY FOR A SEPARATE PERMIT FOR EACH SOURCE. (CHECK AT RIGHT, AND COMPLETE LINES 7, 8, 13, AND 14).					(✓)
PROCESS SOURCE WITH IN-PROCESS FUEL: PRODUCTS OF COMBUSTION CONTACT MATERIALS HEATED. APPLY FOR A SEPARATE PERMIT FOR EACH SOURCE. (CHECK AT RIGHT, AND COMPLETE LINES 7, 8, AND 10 THROUGH 14)					()
NON-PROCESS FUEL BURNING SOURCE: PRODUCTS OF COMBUSTION DO NOT CONTACT MATERIALS HEATED. COMPLETE THIS FORM FOR EACH BOILER OR FUEL BURNER AND COMPLETE AN EMISSION POINT DESCRIPTION FORM (APC 22) FOR EACH STACK. (CHECK AT RIGHT, AND COMPLETE LINES 9 TO 14)					()
7. TYPE OF OPERATION: CONTINUOUS,		BATCH		NORMAL BATCH TIME	NORMAL BATCHES/DAY
()		()			
8. PROCESS MATERIAL INPUTS AND IN-PROCESS SOLID FUELS	DIAGRAM* REFERENCE	INPUT RATES (POUNDS/HOUR)		(FOR APC USE ONLY)	
		DESIGN	ACTUAL	SCC CODE	
A.				/	
B.				/	
C.				/	
D.				/	
E.				/	
F.				/	
G.				/	
TOTALS				/	

* A SIMPLE PROCESS FLOW DIAGRAM MUST BE ATTACHED.

(OVER)

DEC 10 2012

APC 21 (& 24)

9. BOILER OR BURNER DATA: (COMPLETE LINES 9 TO 14 USING A SEPARATE FORM FOR EACH BOILER)					
BOILER NUMBER	STACK NUMBER**	TYPE OF FIRING***	RATED BOILER HORSEPOWER	RATED INPUT CAPACITY (10 ⁶ BTU/HR)	OTHER BOILER RATING (SPECIFY CAPACITY AND UNITS)
N/A	N/A	N/A	N/A	N/A	N/A
BOILER SERIAL NO.		DATE CONSTRUCTED	DATE OF LAST MODIFICATION (EXPLAIN IN COMMENTS BELOW).		
N/A		N/A	N/A		

** BOILERS WITH A COMMON STACK WILL HAVE THE SAME STACK NUMBER.

*** CYCLONE, SPREADER (WITH OR WITHOUT REINJECTION), PULVERIZED (WET OR DRY BOTTOM, WITH OR WITHOUT REINJECTION), OTHER STOKER (SPECIFY TYPE), HAND FIRED, AUTOMATIC, OR OTHER TYPE (DESCRIBE BELOW IN COMMENTS).

10. FUEL DATA: (COMPLETE FOR A PROCESS SOURCE WITH IN-PROCESS FUEL OR A NON-PROCESS FUEL BURNING SOURCE)				STANDBY FUEL TYPE(S) (SPECIFY)			
PRIMARY FUEL TYPE (SPECIFY)							
FUELS USED	ANNUAL USAGE	HOURLY USAGE		% SULFUR	% ASH	BTU VALUE OF FUEL	(FOR APC ONLY) SCC CODE
Diesel #2		DESIGN	AVERAGE				
NATURAL GAS:	10 ⁶ CUFT	CUFT	CUFT	//// ////	//// ////	1,000	
#2 FUEL OIL:	10 ³ GAL	GAL	GAL	.0015% 15 PPM	//// ////		
Diesel #2							
#5 FUEL OIL:	10 ³ GAL	GAL	GAL		//// ////		
#6 FUEL OIL:	10 ³ GAL	GAL	GAL		//// ////		
COAL:	TONS	LBS	LBS				
WOOD:	TONS	LBS	LBS	//// ////	//// ////		
LIQUID PROPANE:	10 ³ GAL	GAL	GAL	//// ////	//// ////	85,000	
OTHER (SPECIFY TYPE & UNITS.):							

11. IF WOOD IS USED AS A FUEL, SPECIFY TYPES AND ESTIMATE PERCENT BY WEIGHT OF BARK


N/A

12. IF WOOD IS USED WITH OTHER FUELS, SPECIFY PERCENT BY WEIGHT OF WOOD CHARGED TO THE BURNER.

N/A

13. COMMENTS

14. SIGNATURE



DATE

11/8/12



NOT TO BE USED FOR TITLE V APPLICATIONS

EMISSION POINT DESCRIPTION

APC 22

PLEASE TYPE OR PRINT AND SUBMIT IN DUPLICATE FOR EACH STACK OR EMISSION POINT.
ATTACH TO THE PERMIT APPLICATION.

1. ORGANIZATION NAME				///	APC COMPANY POINT NO.
American Tower Corporation - East Sevierville # 308917				FOR	
2. EMISSION SOURCE NO. (FROM APPLICATION)		FLOW DIAGRAM POINT NUMBER		///	APC SEQUENCE NO.
E1				APC	
3. LOCATION:	LATITUDE	LONGITUDE	UTM VERTICAL	UTM HORIZONTAL	
122-County Garage Rd. Sevierville, TN	35.876553	-83.4802	276096	3973098	
4. BRIEF EMISSION POINT DESCRIPTION (ATTACH A SKETCH IF APPROPRIATE):				DISTANCE TO NEAREST PROPERTY LINE (FT)	
				3'	


COMPLETE LINES 5 AND 6 IF DIFFERENT FROM THAT ON THE PROCESS OR FUEL BURNING SOURCE DESCRIPTION (APC 21)

5. NORMAL OPERATION:	HOURS/DAY	DAYS/WEEK	WEEK/YEAR		DAYS/YEAR	
Emergency	Varies	Varies	Varies		Varies	
6. PERCENT ANNUAL THROUGHPUT:	DEC.-FEB.	MARCH-MAY	JUNE-AUG.		SEPT.-NOV.	
	25%	25%	25%		25%	
7. STACK OR EMISSION POINT DATA:	HEIGHT ABOVE GRADE (FT)	DIAMETER (FT)	TEMPERATURE (°F)	% OF TIME OVER 125°F	DIRECTION OF EXIT (UP, DOWN OR HORIZONTAL)	
	4'	3"	887		UP	
DATA AT EXIT CONDITIONS:	FLOW (ACTUAL FT ³ /MIN.)	VELOCITY (FT/SEC)	MOISTURE (GRAINS/FT ³)		MOISTURE (PERCENT)	
DATA AT STANDARD CONDITIONS:	FLOW (DRY STD. FT ³ /MIN)	VELOCITY (FT/SEC)	MOISTURE (GRAINS/FT ³)		MOISTURE (PERCENT)	
8. AIR CONTAMINANTS	ACTUAL EMISSIONS			EMISSIONS* EST. METHOD	CONTROL DEVICES*	CONTROL EFFICIENCY%
	EMISSIONS (LBS/HR)		CONCENTRATION			
	AVERAGE	MAXIMUM				
PARTICULATES	0.0346		**	0.0346		
SULFUR DIOXIDE	0.5		***	0.13		
CARBON MONOXIDE	0.202		PPM	0.0505		
ORGANIC COMPOUNDS			PPM			
NITROGEN OXIDES	0.807		PPM	0.202		
FLUORIDES						
OTHER(SPECIFY)	0.75			0.19		
OTHER(SPECIFY)						

(OVER)

9. CHECK TYPES OF MONITORING AND RECORDING INSTRUMENTS THAT ARE ATTACHED:

OPACITY MONITOR (), SO2 MONITOR (), NOX MONITOR (), OTHER (SPECIFY IN COMMENTS) ()

10. COMMENTS**11. SIGNATURE****DATE**

11/9/12

* REFER TO THE BACK OF THE PERMIT APPLICATION FORM FOR ESTIMATION METHOD AND CONTROL DEVICE CODES.

** EXIT GAS PARTICULATE CONCENTRATION UNITS: PROCESS — GRAINS/DRY STANDARD FT3 (70°F); WOOD FIRED BOILERS — GRAINS/DRY STANDARD FT3 (70°F); ALL OTHER BOILERS — LBS/MILLION BTU HEAT INPUT.

*** EXIT GAS SULFUR DIOXIDE CONCENTRATIONS UNITS: PROCESS — PPM BY VOLUME, DRY BASES; BOILERS — LBS/MILLION BTU HEAT INPUT.

GENERAC®

STATEMENT OF EXHAUST EMISSIONS 2011 IVECO DIESEL FUELED GENERATOR

The measured emission values provided here are proprietary to Generac and its' authorized dealers. This information may only be disseminated upon request, to regulatory governmental bodies for emissions permitting purposes or to specifying organizations as submittal data when expressly required by project specifications, and shall remain confidential and not open to public viewing. This information is not intended for compilation or sales purposes and may not be used as such, nor may it be reproduced without the expressed written permission of Generac Power Systems, Inc. The data provided shall not be meant to include information made public by Generac.

Generator Model:	SD080	Aspiration:	Turbocharged/Aftercooled
kW _e Rating:	80	Rated RPM:	1800 RPM
Engine Family:	BVEXL06.7DGB	EPA Certificate #:	VEX-STNRCI-11-15
Engine Model:	F4GE9485A*J	CARB Certificate #:	Not Applicable
Rated Engine Power (BHP)*:	131	SCAQMD CEP#:	511714
Fuel Consumption (gal/hr)*:	6.84	Emission Std. Category:	Tier 3

*Engine Power and Fuel Consumption are declared by the Engine Manufacturer of Record and the U.S. EPA.


Emissions based on declared Rated BHP of specific Engine Models. (These values are Actual Exhaust Emissions during a 5-Mode test based on declared Rated BHP.)

CO	NOx + NMHC	PM	
0.9	3.8	0.16	Grams/kW-hr
0.7	2.8	0.12	Grams/bhp-hr

- The stated values are actual exhaust emission test measurements obtained from an engine representative of the type described above.
- Values based on 5-mode testing are official data of record as submitted to regulatory agencies for certification purposes. Testing was conducted in accordance with prevailing EPA & CARB protocols, which are typically accepted by SCAQMD and other regional authorities.
- No emission values provided above are to be construed as guarantees of emission levels for any given Generac generator unit.
- Generac Power Systems reserves the right to revise this information without prior notice.
- Consult state and local regulatory agencies for specific permitting requirements.
- The emission performance data supplied by the equipment manufacturer is only one element required toward completion of the permitting and installation process. State and local regulations may vary on a case-by-case basis and must be consulted by the permit applicant/equipment owner prior to equipment purchase or installation. The data supplied herein by Generac Power Systems cannot be construed as a guarantee of installability of the generating set.

INDUSTRIAL SALES
P.O. BOX 8 WAUKESHA, WI 53187 262-544-4800 FAX 262-544-4854

DEC 10 2012



THE PROPOSED PROJECT INCLUDES PLACING A 80 KW SHARED GENERATOR IN AN EXISTING CELLULAR TOWER COMPOUND.

PROJECT DESCRIPTION:


CUSTOMER SITE IDENTIFICATION:
SITE NUMBER: 10082979
SITE NAME: N/A



BACKUP POWER PROJECT

ATC SITE IDENTIFICATION:

SITE NUMBER: 308917
SITE NAME: EAST SEVIERVILLE
SITE ADDRESS: 122-COUNTY GARAGE RD.
SEVIERVILLE, TN 37876



PROJECT TEAM

ARCHITECT:
ATC TOWER SERVICES, INC.
1899 LELAND DRIVE, SUITE A
MALETTA, GA 30067
TEL: 678-265-6705
FAX: 678-265-6781
CONTACT: JAMES JUSTICE
A & E MANAGER
LANDLORD:
AMERICAN TOWERS, LLC
10 PRESIDENTIAL WAY
WORLUM, MA 01801
TEL: 781-926-4500
FAX: 781-926-4595
GROUND OWNER:
FRANK GEORGE CATE
1924 WALNUT GROVE RD
SEVIERVILLE, TN 37876
UTILITIES:
POWER COMPANY:
SEVIER COUNTY ELECTRIC SYSTEM
TEL: 865-453-2887
TELEPHONE COMPANY:
BELL SOUTH
TEL: 866-336-8278

PROJECT SUMMARY

GEOGRAPHIC COORDINATES:
LATITUDE: 35° 52' 35.59" N
LONGITUDE: 83° 28' 48.59" W
GROUND ELEVATION: 1041.5 FT.
CODE BLOCK:
BUILDING CODE: 2006 INTERNATIONAL BUILDING CODE
ATTI OPS FOR POWER CUT OVER:
NEED 24 HOUR NOTICE
ERIC BAKER
TEL: 406-623-0081
EMAIL: JB@ATC.COM

PROJECT NOTES

1. THE FACILITY IS UNMANNED.
2. A TECHNICIAN WILL VISIT THE SITE APPROXIMATELY ONCE A MONTH FOR ROUTINE INSPECTION AND MAINTENANCE.
3. THE PROJECT WILL NOT RESULT IN ANY SIGNIFICANT LAND DISTURBANCE OR EFFECT OF STORM WATER DRAINAGE.
4. NO SANITARY SEWER, POTABLE WATER OR TRASH DISPOSAL IS REQUIRED.
5. HANDICAP ACCESS IS NOT REQUIRED.

PROJECT LOCATION DIRECTIONS

FROM NASHVILLE: I-40 EAST TO EXIT 407, HWY 66, TO SEVIERVILLE PROCEED APPROXIMATELY 8.5 MILES, AFTER CROSSING SECOND BRIDGE (LITTLE PIGEON RIVER), TURN LEFT ON HWY 411. GO APPROX 5 1/2 MILES, THEN TURN RIGHT ONTO COUNTY GARAGE RD. JUST PAST (BECK'S HARDWARE). SITE IS IN THE PASTURE ACROSS FROM GRAVEYARD ON RIGHT SIDE OF THE ROAD BEHIND CATTLE GATE. MAKE SURE TO CLOSE GATE.

SHEET INDEX


SHEET NO.	DESCRIPTION	REV.	DATE	BY
T-1	TITLE SHEET, VICINITY MAP AND GENERAL INFORMATION	0	08-22-12	PP
A-1	SITE PLAN	0	08-22-12	PP
A-2	CONCRETE PAD DETAILS	0	08-22-12	PP
A-3	FRAME WIND LOAD CALCULATIONS	0	08-22-12	PP
E-1	WIRING DIAGRAM & FRAME LAYOUT	0	08-22-12	PP
E-2	ELECTRICAL DETAILS	0	08-22-12	PP
G-1	COMPOUND GROUNDING	0	08-22-12	PP
	GENERATOR ASSEMBLY AND INSTALLATION SUPPLEMENT			

© 2012 by ATC IP LLC. All rights reserved.





ATC TOWER SERVICES, INC.
8505 FREEDOM PARKWAY
IRVING, TX 75063
PHONE: (972) 998-8900
FAX: (972) 998-8910
ATC SITE NUMBER:
308917

ATC SITE NAME:
EAST SEVIERVILLE
SITE ADDRESS:
122-COUNTY GARAGE RD.
SEVIERVILLE, TN 37876



DATE: 08-22-12	BY: PP
DESIGNED BY: PP	CHECKED BY: PP
DATE: 08-22-12	DATE: 08-22-12
JOHN C. SANCHEZ	SHEET TITLE:
TITLE SHEET	VICINITY MAP AND GENERAL INFORMATION
SHEET NUMBER:	T-1
REV. A	0



NOTE:
SEE G-1 FOR CABLE & CONDUIT ROUTE DETAILS

ELECTRICAL CONTRACTOR SHALL MAINTAIN FACTORY RECOMMENDED CLEARANCES FOR GENERATOR OR 48" CLEAR ON EACH SIDE OF GENERATOR AND 36" CLEAR ON EACH SIDE OF FRAME. CLEARANCES MAY OVERLAP.

2 TYPICAL BOLLARD INSTALLATION
DETAIL (IF REQUIRED)
SCALE: NOT TO SCALE

ELEVATION VIEW

SCALE
1"=10'-0" (11" X 17")
1"=5'-0" (24" X 36")

1 SITE PLAN

NOTE: LEASE AREA
IS 100' X 100'

[illegible]



The AT&T logo is a registered trademark of AT&T Knowledge Ventures, L.P. All other marks contained herein are the property of their respective owners. © 2004 AT&T Knowledge Ventures, L.P. All rights reserved.



AMERICAN TOWER
ATC TOWER
SERVICES, INC.
 8555 PERSHOP PARKWAY
 SUITE 185
 IRVING, TX 75039
 TEL: 972.399.8900
 FAX: 972.399.8940
 INFO: AMT

ATC SITE NUMBER:
308917

ATC SITE NAME:
EAST
SEVIERVILLE

SITE ADDRESS:
 112 COUNTY CAVENUE RD.
 SEVIERVILLE, TN 37876




SEVIER COUNTY
 TENNESSEE
 1916

OWNER: BT
DESIGNER: BT
DATE: 06-21-04
DATE PLANNED: 06-21-04
DATE BUILT: 06-21-04

SHEET TITLE:
CONCRETE PAD
DETAILS

SHEET NUMBER: A-2
REV: 0



GEN SET SIZE	VOLTS - PHASE	POLE RATING KW - KVA	SIZE OF PLANT GENERATOR SET GENERATOR	MAIN BREAKER (SEE SERVING ANCHOR TYPICAL)	RESERVE FEEDER PANEL/GEN SET BREAKERS TO DISTRIBUTION PANEL / ATS.
500KW	120/240V - 1PH	48KW - 200A	200A	200A C/B INTEGRAL TO GEN SET	1PH/20, 1PH/6 IN 3TC
800KW	120/240V - 1PH	72KW - 300A	400A	200A C/B INTEGRAL TO 800A MMD DISTRIBUTION PANEL	2 LETH OF 3PH/30KVA, 120/200, 12/20 3TC
1200KW	120/240V - 1PH	115KW - 450A	600A	200A C/B INTEGRAL TO 800A MMD DISTRIBUTION PANEL	2 LETH OF 3PH/30KVA, 120/200, 12/20 3TC
1500KW	120/240V - 1PH	135KW - 553A	700A	200A C/B INTEGRAL TO 800A MMD DISTRIBUTION PANEL	2 LETH OF 3PH/30KVA, 120/200, 12/20 3TC

NOTES:

1. SERVICE VOLTAGE FOR EACH CARRIER IS 120/240 1-PHASE, AND SERVICE SIZES ARE TYPICALLY 200A PER CARRIER.
2. DISTRIBUTION PANELS IS 800A, 2-PHASE, 1-PHASE, 200KVA WITH 200A C/B ON THE LISTED CARRIER OUTPUT. PANEL HAS 18 200A BREAKER
3. ALL CARRIER CABLES ARE 1/2" MIN. 120/240V, 1-PHASE PER CARRIER.
4. ALL ELECTRICAL EQUIPMENT IS NEMA 3B RATED.
5. THE GENERATOR ELECTRICAL LOADS ARE ADEQUATE FOR THE CONNECTED LOADS.
6. ALL EQUIPMENT MOUNTINGS SHALL BE PROVIDED WITH EQUIPMENT RAILS TO WITHSTAND PLANT CURRENT AVAILABLE AT PROJECT SITE.
7. A NEW SET OF PLANS WILL BE PROVIDED AND SUBMITTED FOR ADDITIONAL CARRIERS.
8. ALL WORK SHALL COMPLY WITH THE CURRENT VERSION OF THE NEC.
9. FIRST OVERCURRENT PROTECTION DEVICES IS INTEGRAL TO GENERATOR. FEEDER SIZES INDICATED IN TABLE ABOVE ARE DOWNSTREAM OF
11. MAIN BREAKER AT GENERATOR FACTORY INSTALLED, AND THE MAIN BREAKERS RECOMMENDED USE.



**ATC TOWER
SERVICES, INC.**
8505 FREEPORT PARKWAY
SUITE 135
IRVING, TX 75063
PHONE: (972) 999-6900
FAX: (972) 999-6940
NYSE LIST

ATC SITE NUMBER:
308917

ATC SITE NAME
EAST
SEVIERVILLE

SITE ADDRESS:
122-COUNTY GARAGE RD.
SEVERVILLE TN 37876

Peter Adam, Lecturer, P.E.
Tennant, P.E. 115619
276 0414 0876, 0876 0414

123

LEA
BRAD

RE
香江
國貨
米
BANK

30

10

11419

02712323

1997

SECRET


ELECTRICAL

DETAILS


SECRET AND ABOVE

3	2
---	---


2-7-0




1 GROUND ROD DETAIL




2 VERTICAL POST CONNECTED TO RING




3 GENERATOR GROUND RING DETAIL



4 CONDUIT TRENCH DETAIL



5 H-FRAME ELEVATION



6 COMPOUND GROUNDING

NOTE: THE ELECTRICAL CONTRACTOR MAY SELECT TO USE MULTIPLE 42 TINNED COPPER GROUND WIRES IN THE CONDUIT TRENCHES. THIS TABLE PROVIDES THE EQUIVALENCY.

EQUIVALENT WIRE GROUND CHART
42 AWG - 66.36 KCMIL - 0.0231 SQ. IN. - USE (1) #2G
40 AWG - 51.78 KCMIL - 0.0183 SQ. IN. - USE (2) #2G
41/0 - 105.6 KCMIL - 0.0462 SQ. IN. - USE (2) #2G
42/0 - 133.1 KCMIL - 0.0585 SQ. IN. - USE (2) #2G
43/0 - 167.8 KCMIL - 0.1185 SQ. IN. - USE (3) #2G
250 KCMIL - 0.1704 SQ. IN. - USE (4) #2G

NOTE: 1. ELECTRICIAN SHALL VERIFY THAT GENERATOR IS INSTALLED SO THAT ELECTRICAL BACKFEEDS ARE NOT POSSIBLE. 2. ELECTRICIAN SHALL VERIFY THAT GROUNDING IS INSTALLED SO THAT IT MEETS THE REQUIREMENTS OF THE NATIONAL ELECTRICAL CODE. 3. ALL GROUNDING IS CONNECTED TO BESTING TOWER. 4. ALL LIGHTNING GROUNDING SHALL BE FREE OF JUNKS AND SHALL HAVE LONG MONITOR BENDS (MINIMUM 17'). 5. USE 42 AWG SOLID TINNED COPPER WIRE TO EXISTING SECTION 250. 6. FENCE POSTS AND CAPPED ROD FROM GENERATOR GROUND RING

AT&T
ATC TOWER
SERVICES, INC.
8905 REEFER PARKWAY
SUITE 100
DOWNS, TX 75040
PHONE: 972.999.8900
FAX: 972.999.8910
1992 AWT

ATC SITE NUMBER
308917

ATC SITE NAME
EAST
SEVERVILLE

SITE ADDRESS
122 COUNTRY GARDEN RD.
SEVERVILLE, TN 37376

ATC TOWER
SERVICES, INC.
8905 REEFER PARKWAY
SUITE 100
DOWNS, TX 75040
PHONE: 972.999.8900
FAX: 972.999.8910
1992 AWT

ATC SITE NUMBER
308917

ATC SITE NAME
EAST
SEVERVILLE

SITE ADDRESS
122 COUNTRY GARDEN RD.
SEVERVILLE, TN 37376

ATC TOWER
SERVICES, INC.
8905 REEFER PARKWAY
SUITE 100
DOWNS, TX 75040
PHONE: 972.999.8900
FAX: 972.999.8910
1992 AWT

ATC SITE NUMBER
308917

ATC SITE NAME
EAST
SEVERVILLE

SITE ADDRESS
122 COUNTRY GARDEN RD.
SEVERVILLE, TN 37376

GENERAC 80KW


GENERAL ASSEMBLY AND INSTALLATION SUPPLEMENT

100 - 400 Amps,
600 VAC HTS

GENERAC INDUSTRIAL

Automatic Transfer Switches

100 - 400 Amps, 600 VAC



200 Amp HTS NEMA 1

Standard Features

- Single coil design, electrically operated and mechanically held
- Programmable exercise time
- SPD¹ aux contacts
- Main contacts are silver alloy
- Conformer coating protects the printed circuit board
- UL 1008 Listed
- Indicating LEDs for switch position, standby operating, utility available

Optional Accessories

- NEMA 12 enclosure (100-400 Amps)
- NEMA 3R enclosure (4A)

Description

- The Generac HTS Transfer Switch is a "State of the Art" Smart Switch designed to operate in conjunction with the Generac HT100 Series generator controller.
- The HTS Transfer Switch has a 2 wire RS485 communication link to the generator controller.
- The utility voltage is monitored by the HTS along with signal before transfer timing, time delay neutral and inphase transfer.
- Switch operation is initiated by the generator controller.
- All timers and voltage setpoints are programmable through GenLink Communications Software.
- Time delay neutral and inphase monitor are included.

Interconnections

HTS 100-400 Amp

Switches and Indicators:

- System Ready LED
- Switch Position LED's
- Test Switch
- Return to Normal Switch
- Standby Accept Voltage
- Standby Accept Frequency
- Normal Voltage
- Allowable Deviation of Utility
- Line Interruption Delay
- Engine Warmup Time
- Minimum Run Time
- Return to Utility Timer
- Engine Shutdown Timer
- Signal Before Transfer Inset
- Transfer Type
- Phase Difference for Inphase Transfer

- Standby Operating LED
- Utility Available LED
- Fast Test Switch
- Safety Disconnect Switch


Standby Accept Voltage	85-95%
Standby Accept Frequency	65-95%
Normal Voltage	1 Volt In/Out
Allowable Deviation of Utility	1-100%
Line Interruption Delay	1-100%
Engine Warmup Time	1-300 Seconds
Minimum Run Time	5-60 Minutes
Return to Utility Timer	1-30 Minutes
Engine Shutdown Timer	1-30 Minutes
Signal Before Transfer Inset	1-30 Seconds
Transfer Type	Inphase Time Delay Neutral
Phase Difference for Inphase Transfer	7-10 Degrees

Withstand Current - 600 Volt HTS Series

HTS RATED AMPS	100	150	200	300	400
FUSE PROTECTED					
Maximum RMS Symmetrical Fault Current - Amps	200,000	200,000	200,000	200,000	200,000
Maximum Fuse Size - Amps	200	400	400	600	600
Fuse Class	JT	JT	JT	JT	JT
CIRCUIT BREAKER PROTECTED					
Maximum RMS Symmetrical Fault Current - Amps	14,000	25,000	25,000	35,000	35,000
Protective Device Continuous Rating (Max) - Amps	150	300	300	600	600

* Tested in accordance with the withstand and closing requirements of UL 1008 and CSA Standards.
* Current ratings are listed @ 480 VAC.

Unit Dimensions




HTS RATED AMPS	VOLTAGE	ENCLOSURE HEIGHT	ENCLOSURE WIDTH	WALL MOUNT BOLT PATTERN	ENCLOSURE DEPTH	WEIGHT (lbs.)
100	ALL	35	24	M1	10	180
150-200	120/240	35	24	M2	10	185
150-200	120/208	36	24	M1	10	185
150-200	277/480	48*	30*	M2	12	255
300-400	120/240	36	24	M1	10	245
300-400	120/208	36	24	M2	10	245
300-400	277/480	48*	30*	M2	12	325

Terminal Lug Wire Ranges

HTS RATED AMPS	CONDUCTOR TERMINALS (1 USE PER POLE)	# LUGS	NEUTRAL BAR**	GROUND LUG (1 PROVIDED)
100	20 - 14 AWG	4	20 - 14 AWG	20 - 14 AWG
150	4000CM - 4 AWG	4	3500CM - 6 AWG	3500CM - 6 AWG
200	4000CM - 4 AWG	4	3500CM - 6 AWG	3500CM - 6 AWG
300	6000CM - 4 AWG	4	6000CM - 4 AWG	3500CM - 6 AWG
400	or 2 - 12500CM - 10 AWG	4	12500CM - 10 AWG**	3500CM - 6 AWG
	or 2 - 12500CM - 10 AWG	4	6000CM - 4 AWG	3500CM - 6 AWG


* Not included in HTS with switched neutral. ** Allowable wire range in brackets is for 2 wires per lug.



NOTE:
1. ORIGINAL CURRENT TRANSFORMERS.

PART NO.	RATIO	MODEL NO.	#%	VA	OHMS	"A"	"B"	"C"
0F7784A	100:1A	635-100-01-136	1	31	.95	.65	.28	30.5
0F7784B	200:1A	635-200-01-136	1	5	.45	.65	.28	30.5
0F7784C	300:1A	A-300-01-136	1	4.5	.06	.112	.571	27.4
0F7784D	400:1A	A-400-01-136	1	4	.11	.112	.571	27.4
0F7784E	500:1A	A-500-01-136	1	6.5	.13	.112	.571	27.4
0F7784F	600:1A	A-600-01-136	1	7.5	.15	.112	.571	27.4
0F7784G	800:1A	AW-800-01-136	1	10	.20	.143.5	.89	29.2
0F7784H	1000:1A	AW-1000-01-136	1	12	.22	.143.5	.89	29.2
0F7784J	1500:1A	AW-1500-01-136	1	15	.50	.143.5	.89	29.2
0F7784K	2000:1A	AW-2000-01-136	1	12	.67	.143.5	.89	29.2
0F7784L	3000:1A	AW-3000-01-136	1	25	1.0	.143.5	.89	29.2

2 CURRENT FLOW METER IN ATS



NOTES:
1. CONNECT TO TENANT BREAKER AT METER.
2. CONNECT TO DISTRIBUTION CENTER BRANCH BREAKER.

GENERAC

Highway 59 & Hillside Rd.
Waukesha, WI 53188
Phone 262-544-4811

Ref: All Generac Power Systems fuel tank bases supplied from the factory are manufactured and labeled per U.L. 142 and are warranted through Generac Power Systems.

UL registration number: MH18459

U.L. 142 DOUBLE WALL FUEL TANK BASE SPECIFICATION

Fuel tank base construction:

- Be constructed in accordance with Underwriters Laboratories Standard UL-142. Be constructed in accordance with Flammable and Combustible Liquids Code, NFPA 30; The Standard for Installation and use of Stationary Combustible Engine and Gas Turbines, NFPA 37; and The Standard for Emergency and Standby Power Systems, NFPA 110. Include reinforced steel box channel for generator support, with load rating of 5,000 lbs. per gen-set mounting hole location. Full height gussets shall be provided at gen-set mounting holes. Be shipped with a certificate of Structural/Mechanical Integrity, certifying that it has met standards through rigorous testing and has demonstrated specified capabilities.

Sub Base Tank Testing:

Primary tank and secondary containment basin sections shall be pressurized at 3-5 psi and leak-checked to ensure integrity of sub base weld seams per U.L. 142 standards

Sub Base Tank Fittings:

The sub base tank shall include the following fittings:

- Appropriately sized NPT
- Fuel supply fuel return fitting
- NPT for normal vent, sized as appropriate NPT for emergency vent, sized as appropriate
- 2" NPT for manual fill
- NPT for level gauge, sized as appropriate.
- 2" NPT for electronic fuel level; includes Low fuel alarm, High fuel level alarm
- NPT fitting for leak detection alarm

Fuel Level Gauge

The sub base tank shall include a direct-reading fuel level gauge.

Low Fuel Level

Factory Pre-set at 40% remaining for Alarm
Factory Pre-set at 20% remaining for Shut-down

High Fuel Level

Factory Pre-set at 90% full for Alarm


Fuel Containment Basin

Sub base tank shall include a welded steel containment basin, sized at a minimum of 110% of the tank capacity to prevent escape of fuel into the environment in the event of a tank rupture. A fuel containment basin leak detector switch shall be provided.

Sub Base Tank Venting

Normal and Emergency Venting:


Normal and Emergency venting shall be sized per U.L. 142 specifications for wetted surface area of tank.




NOTE: POLARIS TAP MUST BE SECURELY WRAPPED WITH COMMERCIAL GRADE NYLON ELECTRICAL TAPE AFTER INSTALLATION IS COMPLETE

NOTE: BONDING JUMPER/ GROUNDING ELECTRODE CONDUCTOR SHALL BE #4 CU FOR 200A, PER NEC TABLE 250.66.


PER NEC 312.8(3), PROVIDE WARNING LABEL (PHENOLIC PLATE) ON ENCLOSURE CONTAINING POLARIS TAP SPECIFYING LOCATION OF MEANS OF DISCONNECT FOR FEEDERS BEING SPLICED.



MULTI-TENANT METER OPTION
SCALE NOT TO SCALE




NOTE: POLARIS TAP MUST BE SECURELY WRAPPED WITH COMMERCIAL GRADE NYLON ELECTRICAL TAPE AFTER INSTALLATION IS COMPLETE



ALTERNATE NEUTRAL CONNECTION
FOR MULTI-TENANT METER OPTION
SCALE NOT TO SCALE

THE ALTERNATE NEUTRAL CONNECTION DETAIL IS INTENDED TO SHOW NEUTRAL CONNECTIONS ONLY. ALL OTHER (NON-NEUTRAL) CONNECTIONS SHOWN ON THE MULTI-TENANT METER DETAIL TO THE LEFT ARE OMITTED FOR CLARITY.



DL / C/L INSTRUCTIONS
REF # DESCRIPTION
BELL TEST _____
HIPOT _____
S/T _____



GENERAL INFORMATION		[SECTION 1 OF 1]	
SERVICE VOLTAGE:	120/240V 1PH 3W	ENCLOSURE TYPE:	30
BUS RATING & TYPE:	800A ALUMINUM	NEUTRAL BARS:	800A
GROUND BAR:	SLO SLOTTED ALUMINUM AL OR CU CABLE		
S.C. RATING:	22K A.I.C. FULLY RATED		
MAIN DEVICE TYPE:	MAIN LUGS ONLY, BOTTOM CABINETS		
MAIN TERMINALS:	MECHANICAL - (3) #2-500 KCMIL (CU/AL)		
NEUTRAL TERMINALS:	MECHANICAL - (3) #2-500 KCMIL (CU/AL)		
BLOCK CAVITIES NO.:	PROG 457		
TRIM:	COMPLETE ENCLOSURE (INCLUDES TRIM)		
SLURFACE MOUNTED:			
BOX DIMENSIONS:	57" 1/4" H x 24" 1/2" W x 12 1/2" D (32 1/2" H x 24 1/2" W x 12 1/2" D)		
MAIN GROUND BAR:	120/240V 1PH 3W		
LEFT-SIDE (112 Dmm) RIGHT-SIDE (112 Dmm)			
FINISH NAMEPLATE:	(1) 800A		
TYPE:	PLASTIC ADHESIVE-REMOVED		
COLOR:	WHITE WITH BLACK LETTERS		
UL:			
SERVICE ENTRANCE LABEL:			
TRIM LOOK: HANDLE & LOCK ASSEMBLY			
CIRCUIT DIRECTOR: PLASTIC SLEEVE WITH CARD			
PRINTED BOX AND 01			
PLANT INFORMATION		PART INFORMATION	
UL LABEL:		PART NUMBER	QTY
GROUND BAR:		7494A04-01	1
NEUTRAL:		657C07B003	1
GROUND BAR, AL/CU:		657C07B003	1
CHASSIS ASSEMBLY:		657C07B003	1
LUG ASSEMBLY:		657C07B003	1
NEUTRAL BAR:		657C07B003	1
DEAD FRONT COVER:		657C07B003	1
COVER PACKAGING:		657C07B003	1
DEAD FRONT COVER ASSEMBLY:		657C07B003	1
PACKAGING:		657C07B003	1

NOTES:



Spot _____ Final Inspection _____

DISTRIBUTION PANEL

SCALE: NOT TO SCALE



SECTION 1
A/A



DISTRIBUTION PANEL DETAILS

SCALE: NOT TO SCALE

SD080

GENERAC INDUSTRIAL


Industrial Diesel Generator Set

EPA Emissions Certification: Tier III

80 kW Diesel

Standby Power Rating
100 kVA 80 kW / 60 Hz

Prime Power Rating
90 kVA 72 kW / 60 Hz



features

benefits

- GENERATOR SET**
- PROTECTED & TORQUALLY TESTED
 - UL2080 TESTED
 - RE-PROTECT PAINT SYSTEM
 - WIDE RANGE OF ENCLOSURES AND TANKS
- ENGINE**
- EPA TIER COMPLIANT
 - INDUSTRIAL TESTED, DIESELIC APPROVED
 - POWERMANAGED OUTPUT
 - INDUSTRIAL GRADE
- ALTERNATOR**
- TWO PHASE WITH
 - LINE WOUND ROTOR & EXCITER
 - CLASS H INSULATION
 - DIGITAL SPEED VOLTAGE CONTROL
- CONTROLS**
- ENCAPSULATED BOARD BY TELEDYNE HANESS
 - 4-20VMA VOLTAGE TO CURRENT TRANSDUCER
 - STATE-OF-THE-ART TECHNOLOGY
 - ADVANCED PROTECTIVE & COMMUNICATION
- PROVIDES A MODULAR UNIT**
- ENSURES A QUALITY PRODUCT**
- APPROVES RESISTANCE TO ELEMENTS**
- PROVIDES A SPACE SAVING SOLUTION**
- SWAGNER/VENTILATED**
- ENHANCES INDUSTRIAL, TRANSPORTATION**
- ENHANCED FOR PERFORMANCE**
- IMPROVES LONGEVITY AND RELIABILITY**
- ENSURES MAXIMUM, 20% HARMONIC**
- IMPROVES COOLING**
- HEAT TOLERANT DESIGN**
- FAST AND ACCURATE RESPONSE**
- ENVIRONMENTAL RESISTANT**
- INHERENTLY SAFE AND RELIABLE**
- PROTECTS VIBRATION RESISTANCE**
- IMPROVED RELIABILITY**

primary codes and standards



SD080

application and engineering data

GENERAC INDUSTRIAL

80 kW Diesel

ENGINE SPECIFICATIONS

General	
Make	Inco / JPT
EPA Emissions Compliance	Tier III
EPA Emissions Reference	See Emissions Data Sheet
Cylinder #	4
Type	Direct
Displacement - L (cu in)	4.5 (274)
Bore - mm (in)	105 (4.1)
Stroke - mm (in)	132 (5.2)
Compression Ratio	17.5:1
Inlet Air Method	Turbocharged
Cylinder Head Type	Aluminum
Piston Type	Forged Steel
Connecting Rod	Forged Steel
Engine Block Type	Cast Iron / Wet Sump
Engine Governor	
Governor	Electronic
Frequency Regulation (Steady State)	+/- 0.25%
Lubrication System	
Oil Pump Type	Gear
Oil Filter Type	Fold Flow
Crankcase Capacity - L (gal) (qt)	13.6 (3.6) (14.6)
Cooling System	
Water Pump Type	Best Design Centrifugal
Fan Type	Forward Curved
Fan Blade Number	2389 (10)
Fan Diameter (in)	50
Water Flow (GPM)	120
Water Pressure (PSI)	120
Constant Speed Standard Voltage	120
Fuel System	
Fuel Type	Ultra Low Sulfur Diesel Fuel
Fuel Specifications	ASTM
Fuel Injection (Inboard)	5
Fuel Injection Pump Make	Isuzu
Injection Type	Common Rail
Engine Type	Direct Injection
Fuel Supply Line - mm (in)	1/4 inch NPT
Fuel Return Line - mm (in)	1/4 inch NPT
Exciter Electrical System	
System Voltage	120VAC
Exciter Output	900W
Exciter Input	700W
Battery Group	31C
Battery Voltage	12 Volt DC
Grounding	Negative

ALTERNATOR SPECIFICATIONS

Model	380 mm Enclosure
Field Type	4
Field Type	Revolving
Insulation Class - Stator	H
Insulation Class - Rotor	H
Total Harmonic Distortion (THD)	< 5%
Telephone Interference Factor (TIF)	< 50
Interference Type	ONCE THE LINES & CABLES ARE PROTECTED
Load Capacity - Steady	72
Load Capacity - Prime	72
Prime/Standby Short Circuit Test	Y
Voltage Regulation Type	
Regulation Accuracy (Steady State)	+/- 0.25%
Codes and Standards Compliance (Where Applicable)	
NFPA 99	
NFPA 110	
ISO 12869	
ISO 12865	
ISO 12865	
ISO 3046	
BS5514	
SAE J1349	
DIN 4271	
IEEE C42.41 TESTING	
NECA (CS 1)	

Standby: Applicable for a varying emergency load for the duration of a utility power outage with no overload capacity. (Max. load factor = 70%)

Prime: Applicable for supplying power to a varying load in lieu of utility for an unlimited amount of running time. (Max. load factor = 100%)

120VAC

SD080

operating data (60Hz)

POWER RATINGS PLAN

Single-Phase 120/240VAC @ 1.0pf
Three-Phase 120/240VAC @ 0.8pf
Three-Phase 120/240VAC @ 0.9pf
Three-Phase 277/480VAC @ 0.8pf
Three-Phase 346/600VAC @ 0.8pf



STARTING CAPACITIES (KVA)

	STANDBY		PRIME	
	60	Amperes	72	Amperes
Single-Phase	80	333	72	300
Three-Phase	80	378	72	250
Three-Phase	80	241	72	217
Three-Phase	80	128	72	108
Three-Phase	80	76	72	87

	STANDBY		PRIME	
	60	Amperes	72	Amperes
Single-Phase	80	333	72	300
Three-Phase	80	378	72	250
Three-Phase	80	241	72	217
Three-Phase	80	128	72	108
Three-Phase	80	76	72	87

KVA V. Voltage DB

	480VAC		208/240VAC	
	AV	AV	AV	AV
Alternator	159	139	206	259
Standby	80	59	117	147
Prime	100	79	137	167
Load 1	120	99	157	197
Load 2	140	119	177	217
Load 3	160	139	197	237
Load 4	180	159	217	257
Load 5	200	179	237	277
Load 6	220	199	257	297
Load 7	240	219	277	317
Load 8	260	239	297	337
Load 9	280	259	317	357
Load 10	300	279	337	377
Load 11	320	299	357	397
Load 12	340	319	377	417
Load 13	360	339	397	437
Load 14	380	359	417	457
Load 15	400	379	437	477
Load 16	420	399	457	497
Load 17	440	419	477	517
Load 18	460	439	497	537
Load 19	480	459	517	557
Load 20	500	479	537	577
Load 21	520	499	557	597
Load 22	540	519	577	617
Load 23	560	539	597	637
Load 24	580	559	617	657
Load 25	600	579	637	677
Load 26	620	599	657	697
Load 27	640	619	677	717
Load 28	660	639	697	737
Load 29	680	659	717	757
Load 30	700	679	737	777
Load 31	720	699	757	797
Load 32	740	719	777	817
Load 33	760	739	797	837
Load 34	780	759	817	857
Load 35	800	779	837	877
Load 36	820	799	857	897
Load 37	840	819	877	917
Load 38	860	839	897	937
Load 39	880	859	917	957
Load 40	900	879	937	977
Load 41	920	899	957	997
Load 42	940	919	977	1017
Load 43	960	939	997	1037
Load 44	980	959	1017	1057
Load 45	1000	979	1037	1077
Load 46	1020	999	1057	1097
Load 47	1040	1019	1077	1117
Load 48	1060	1039	1097	1137
Load 49	1080	1059	1117	1157
Load 50	1100	1079	1137	1177
Load 51	1120	1099	1157	1197
Load 52	1140	1119	1177	1217
Load 53	1160	1139	1197	1237
Load 54	1180	1159	1217	1257
Load 55	1200	1179	1237	1277
Load 56	1220	1199	1257	1297
Load 57	1240	1219	1277	1317
Load 58	1260	1239	1297	1337
Load 59	1280	1259	1317	1357
Load 60	1300	1279	1337	1377
Load 61	1320	1299	1357	1397
Load 62	1340	1319	1377	1417
Load 63	1360	1339	1397	1437
Load 64	1380	1359	1417	1457
Load 65	1400	1379	1437	1477
Load 66	1420	1399	1457	1497
Load 67	1440	1419	1477	1517
Load 68	1460	1439	1497	1537
Load 69	1480	1459	1517	1557
Load 70	1500	1479	1537	1577
Load 71	1520	1499	1557	1597
Load 72	1540	1519	1577	1617
Load 73	1560	1539	1597	1637
Load 74	1580	1559	1617	1657
Load 75	1600	1579	1637	1677
Load 76	1620	1599	1657	1697
Load 77	1640	1619	1677	1717
Load 78	1660	1639	1697	1737
Load 79	1680	1659	1717	1757
Load 80	1700	1679	1737	1777
Load 81	1720	1699	1757	1797
Load 82	1740	1719	1777	1817
Load 83	1760	1739	1797	1837
Load 84	1780	1759	1817	1857
Load 85	1800	1779	1837	1877
Load 86	1820	1799	1857	1897
Load 87	1840	1819	1877	1917
Load 88	1860	1839	1897	1937
Load 89	1880	1859	1917	1957
Load 90	1900	1879	1937	1977
Load 91	1920	1899	1957	1997
Load 92	1940	1919	1977	2017
Load 93	1960	1939	1997	2037
Load 94	1980	1959	2017	2057
Load 95	2000	1979	2037	2077
Load 96	2020	1999	2057	2097
Load 97	2040	2019	2077	2117
Load 98	2060	2039	2097	2137
Load 99	2080	2059	2117	2157
Load 100	2100	2079	2137	2177
Load 101	2120	2099	2157	2197
Load 102	2140	2119	2177	2217
Load 103	2160	2139	2197	2237
Load 104	2180	2159	2217	2257
Load 105	2200	2179	2237	2277
Load 106	2220	2199	2257	2297
Load 107	2240	2219	2277	2317
Load 108	2260	2239	2297	2337
Load 109	2280	2259	2317	2357
Load 110	2300	2279	2337	2377
Load 111	2320	2299	2357	2397
Load 112	2340	2319	2377	2417
Load 113	2360	2339	2397	2437
Load 114	2380	2359	2417	2457
Load 115	2400	2379	2437	2477
Load 116	2420	2399	2457	2497
Load 117	2440	2419	2477	2517
Load 118	2460	2439	2497	2537
Load 119	2480	2459	2517	2557
Load 120	2500	2479	2537	2577
Load 121	2520	2499	2557	2597
Load 122	2540	2519	2577	2617
Load 123	2560	2539	2597	2637
Load 124	2580	2559	2617	2657
Load 125	2600	2579	2637	2677
Load 126	2620	2599	2657	2697
Load 127	2640	2619	2677	2717
Load 128	2660	2639	2697	2737
Load 129	2680	2659	2717	2757
Load 130	2700	2679	2737	2777
Load 131	2720	2699	2757	2797
Load 132	2740	2719	2777	2817
Load 133	2760	2739	2797	2837
Load 134	2780	2759	2817	2857
Load 135	2800	2779	2837	2877
Load 136	2820	2799	2857	2897
Load 137	2840	2819	2877	2917
Load 138	2860	2839	2897	2937
Load 139	2880	2859	2917	2957
Load 140	2900	2879	2937	2977
Load 141	2920	2899	2957	2997
Load 142	2940	2919	2977	3017
Load 143	2960	2939	2997	3037
Load 144	2980	2959	3017	3057
Load 145	3000	2979	3037	3077
Load 146	3020	2999	3057	3097
Load 147	3040	3019	3077	3117
Load 148	3060	3039	3097	3137
Load 149	3080	3059	3117	3157
Load 150	3100	3079	3137	3177
Load 151	3120	3099	3157	3197
Load 152	3140	3119	3177	3217
Load 153	3160	3139	3197	3237
Load 154	3180	3159	3217	3257
Load 155	3200	3179	3237	3277
Load 156	3220	3199	3257	3297
Load 157	3240	3219	3277	3317
Load 158	3260	3239	3297	3337
Load 159	3280	3259	3317	3357
Load 160	3300	3279	3337	3377
Load 161	3320	3299	3357	3397
Load 162	3340	3319	3377	3417
Load 163	3360	3339	3397	3437
Load 164	3380	3359	3417	3457
Load 165	3400	3379	3437	3477
Load 166	3420	3399	3457	3497
Load 167	3440	3419	3477	3517
Load 168	3460	3439	3497	3537
Load 169	3480	3459	3517	3557
Load 170	3500	3479	3537	3577
Load 171	3520	3499	3557	3597
Load 172	3540	3519	3577	3617
Load 173	3560	3539	3597	3637
Load 174	3580	3559	3617	3657
Load 175	3600	3579	3637	3677
Load 176	3620	3599	3657	3697
Load 177	3640	3619	3677	3717
Load 178	3660	3639	3697	3737
Load 179	3680	3659	3717	3757
Load 180	3700	3679	3737	3777
Load 181	3720	3699	3757	3797
Load 182	3740	3719	3777	3817
Load 183	3760	3739	3797	3837
Load 184	3780	3759	3817	3857
Load 185	3800	3779	3837	3877
Load 186	3820	3799	3857	3897
Load 187	3840	3819	3877	3917
Load 188	3860	3839	3897	3937
Load 189	3880	3859	3917	3957
Load 190	3900	3879	3937	3977
Load 191	3920	3899	3957	3997
Load 192	3940	3919	3977	4017
Load 193	3960	3939	3997	4037
Load 194	3980	3959	4017	4057
Load 195	4000	3979	4037	4077
Load 196	4020	3999	4057	4097
Load 197	4040	4019	4077	4117
Load 198	4060	4039	4097	4137
Load 199	4080	4059	4117	4157
Load 200	4100	4079	4137	4177
Load 201	4120	4099	4157	4197
Load 202	4140	4119	4177	4217
Load 203	4160	4139	4197	4237
Load 204	4180	4159	4217	4257
Load 205	4200	4179	4237	4277
Load 206	4220	4199	4257	4297
Load 207	4240	4219	4277	4317
Load 208	4260	4239	4297	4337
Load 209	4280	4259	4317	4357
Load 210	4300	4279	4337	4377
Load 211	4320	4299	4357	4397
Load 212	4340	4319	4377	4417
Load 213	4360	4339	4397	4437
Load 214	4380	4359	4417	4457
Load 215	4400	4379	4437	4477
Load 216	4420	4399	4457	4497
Load 217	4440	4419	4477	4517
Load 218	4460	4439	4497	

[illegible][illegible]

APPROX. NET WEIGHT VITAMIN PUL. CONJEST PHARMACEUTICALS INC.

REDUCE DAILY GROSS FOR INSTALLATION FUEL TANK BOARDS EMISSION

GEODAC POWER SYSTEMS HAS THE COMPONENTS OF THIS ANALYSIS WHICH IS SUPPORTED BY EXPERIMENTAL AND TEST DATA. IT IS REQUESTED THAT YOU ADVISE US OF ANY COMMENTS OR CORRECTIONS TO THE COMMENTS LISTED HEREIN BY GEODAC POWER SYSTEMS.

GENERAC POWER SYSTEMS

Waukegan
P.O. BOX 8
WAUKEGAN, ILL 60087

P.O. BOX 8
WAKESHA, WIS. 53187

U. D. GOSWAMI
P.O. BOX 8
WAJIKESHA, WIS. 53187

SD80
DIESEL 4.5L IVECO
TURBOCHARGED & AFTERCOOLED

**TURBOCHARGED & AFTERCOOLED
SOUND ATTENUATED ENSL, LVL 2**



W/ 300 GALLON FTB

FILE NAME	0H5302C-B ATC.DWG			SIZE	H
SCALE	N/A	FIRST USE	D45L	IVECD	
DWG. NO.	0H5302C-ATC B				
				REV	

N/A	USE	D4.5L	IVECD
DWG. NO.			REV

REC'D
REV

INSTALLATION DRAWING




ITEM #	TANK FITTING	FUNCTION
1	3/8" NPT COUPLING	FUEL SUPPLY
2	3/8" NPT COUPLING	FUEL RETURN
3	4" NPT WELD FLANGE	EMERGENCY VENT (OUTER)
4	4" NPT WELD FLANGE	FUEL LEVEL
5	2" NPT WELD FLANGE	FUEL FILL
6	4" NPT WELD FLANGE	EMERGENCY VENT (INNER)
7	2" NPT WELD FLANGE	VENT
8	3/4" NPT COUPLING	DRAIN
9	Ø22 HOLE	LEAK DETECTOR

TANK P/N	0H480805T03	0H480905T03	0H480005T03
DIM "A"	330 (13)	635 (25)	940 (37)
TOTAL TANK CAPACITY	318 (94)	734 (94)	1154 (305)
USABLE TANK CAPACITY	289 (79)	716 (89)	1134 (300)
DRY WEIGHT (EST)	237 (522)	344 (758)	445 (982)

NOTES:
1) ALL DIMENSIONS ARE:
LENGTH: mm (inch)
WEIGHT: kg (lbs)
CAPACITY: L (gal)

2) UL #42 LISTED



DRAWING CREATED FROM PRO/ENGINEER
3D FILE. ECO MODIFICATION TO BE
APPLIED TO SOLID MODEL ONLY.

INSTALLATION DRAWING

GENERAL: THIS DRAWING IS THE PROPERTY OF GENERAC. IT IS TO BE USED ONLY FOR THE SPECIFIC TANK AND MODEL NUMBER INDICATED. IT IS NOT TO BE REPRODUCED OR COPIED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF GENERAC. © 2000 GENERAC INDUSTRIES, INC.


TITLE
B-GROUP, DW TYPE 2 TANKS

ISSUE DATE:	10/02/05	REV	D
SIZE:	CAGE NO. 0H4610A	REV	D
SCALE:	0.075	WT-KG	1 of 1

G8500 Series American Tower Installation

This note is for Generac H Panel + HTS installations for American Tower.


1. Unpack the monitor, the antenna, and the data / power cable. The data / power cable is black, with DB9 data connectors on two ends, and a separate pig tail with red and black wire emerging from one of the connectors, labeled OMNIMETRIX END. Make sure that all the components are in good condition, looking for shipping damage.
2. Place the antenna on the roof of the genset, and route the antenna cable through the louvers down into the area of the genset control. BE SURE to provide a drip loop lower than the monitor to keep water from running down the antenna cable into the monitor connection. If the roof is aluminum (non-magnetic), simply mount the antenna near the roof line on the steel side walls.
3. Attach the monitor to the top of the genset control enclosure, as shown.
4. Route the power pigtail with the red and black wires through the cable entry on the back of the genset control, by raising the cable through.
5. Tighten the gate screws back!
6. Attach the black wire to the ground terminal, labeled 0 on the right hand end of the terminal strip inside the genset control enclosure. Attach the red wire to the Battery+ terminal on the left hand end of the terminal strip. On 12V systems, it will be labeled "15". On 24V systems, it will be labeled "220A".
7. Attach the Antenna Cable to the front of the monitor, thumb tight.
8. Plug on the data cable, labeled "OmniMetric End" to the front of the monitor. Tighten screws.
9. Plug the data cable end labeled "Generac End" onto the Generac data connector.
10. Turn on the monitor.
11. Confirm that the LEDs light up and blink if not, check for power on the terminal strip. If, after 5 minutes, the only LED lit is the Power LED, check the antenna mount and cable connection.
12. Allow 15 minutes for the monitor to log into the network, and then call OmniMetric at the number below to confirm installation.



Antenna

Install: on or near top of genset.
OK to install: on genset side
if roof is aluminum.

Notes:
- No RF cables to roof, if desired.
- Remove magnet cover from
- Remove nut and magnet
- Drill hole for studs
- Reinstall nut



9 Socket Connector
Labeled "OmniMetric End"
Connect to OMX 9 Pin Connector



9 Socket Connector
Labeled "Generac End"
Connect to H Panel Diagnostic Port

Generac Wire 15 for 12 V System
Or Wire 220A for 24V System

General Wiring Steps:

1. Install Antenna on or near roof.
2. Connect the Red and Black power wires to the Terminal Strip TB3
3. Connect DB9 connector to the OMX unit.
4. Make sure it is the end marked OMNIMETRIX END !
5. Connect DB9 connector to the Generac Diagnostic Port
6. Make sure it is the end marked GENERAC END !
7. Turn on Power Switch on the OMX unit.
8. LEDs should begin to flash.
9. If not, check power connections with volt meter.
10. Wait 15 minutes for unit to make online connection.
11. Call OMX at 770-289-8012 to confirm operation.


OmniMetric LLC		
G8500 - Generac H Panel		
George P Burdell	Rev 1.0	2011040100
3/29/2011		



QTY	REQD	SIZE	TOTAL LENGTH	TOTAL WEIGHT (LBS)	TYPE	BENDING DIAGRAM	
						DIMENSION	
10	1/2"	0.5"	-	-	FERRULE WING		
10	1/2"	FERRULE PLASTIC CAP	-	-			
5	#4	7'-9 1/16"	39'			A-7'-9 1/16"	
22	#4	4'-1"	60'			A-4'-1"	
4	#4	7'-9 3/8"	31'		STRAIGHT	A-7'-9 3/8"	
6	#4	9 1/4"	3			A-9 1/4"	

STANDARD REBAR SIZES & WEIGHTS

BAR NO.	LB PER FT.	DIAM. INCHES	GRADE
4	447.6	500	60



CONCRETE PAD CONSTRUCTION NOTES

1. ALL REBAR (HORIZONTAL & VERTICAL) SHALL BE SECURELY WIRE TIED TO PREVENT CORROSION DURING POURING OF CONCRETE.
2. CONCRETE TO HAVE A MINIMUM COMPRESSIVE STRENGTH OF 4000 PSI.
3. REINFORCED CONCRETE CONSTRUCTION AND MATERIALS SHALL BE IN ACCORDANCE WITH ACI STANDARDS 318.
4. MINIMUM CONCRETE COVER OVER REBAR IS 1 1/4".
5. REINFORCING MATERIAL SHALL BE IN ACCORDANCE WITH ASTM SPECIFICATION A615-85.

CONCRETE PAD AND EMBEDMENT TOLERANCES

1. EMBEDMENTS, PLUS OR MINUS 1/16".
2. CONCRETE DIMENSIONS, PLUS OR MINUS 1/4".
3. REINFORCING STEEL PLACEMENT, PLUS OR MINUS 1/4" INCLUDING CONCRETE COVER.

NOTES

1. FOUNDATION WAS DESIGNED BY ASSUMING ALLOWABLE SOIL BEARING CAPACITY OF 1000 PSI. THE SOIL BEARING CAPACITY FOR EACH SITE MUST BE VERIFIED DURING THE SITE SPECIFIC GEOTECH REPORT. IF SHALLOW (GROUND WATER) (< 3 FT.) WAS REPORTED, A FURTHER REVIEW OF THE DESIGN OR SPECIAL DESIGN MAY BE REQUIRED.
2. THE SOIL UNDERNEATH THE CONCRETE PAD MUST BE FREE OF ORGANIC MATTER OR OTHER DELETERIOUS SUBSTANCES, AND SHOULD BE COMPACTED AND LEveled BEFORE PLACING THE FOUNDATION PAD SHALL BE DETAILED LEVEL, TO WITHIN +/- 1/8".
3. CONCRETE SLABS: 1'-2".
4. CONCRETE VOLUME: 0.78 CUBIC YARDS.

DESIGN

1. MAXIMUM DESIGN BASIC WIND SPEED (3-SECOND GUST): 90 MPH FOR GENERATOR MODELS SD080 AND SD080

PRE-CAST GENERATOR PAD




ATC TOWER SERVICES, INC.
8805 TOWERWAY
SUITE 135
IRVING, TX 75063
PHONE: (972) 999-0900
FAX: (972) 999-0900
WWW.ATC.COM

ATC SITE NUMBER:
308917

ATC SITE NAME:
EAST SEVIERVILLE

SITE ADDRESS:
122 COUNTY GARAGE RD.
SEVIERVILLE, TN 37876



CONCRETE PAD DETAILS
SHEET NUMBER: **A-2** OF **0**


Note: This design or combination for the H-Frame will be valid for all 800w and 1500w generation sales with same or less design base wind speed as specified below.

A. Design Loads

ASCE 3 Sec. Wind Speed for this tower site: $V_{w} = 90$ MPH

$$K_{-2} := 0.85 \quad K_0 := 1.0 \quad K_1 := 0.95 \quad C_{-2} := 1.2 \quad Q_1 := 1.0$$

Wind pressure per ASCE: $q = 0.00256 \cdot K_z \cdot G \cdot C_{fe} \cdot V^2 \cdot I \cdot K_{xt} \cdot X_d$ $q = 20.093$ Ps



The factored reactions used for the peer program (See the attached calculations)

$$M_{\mathrm{C}} = M_{\mathrm{Cmax}} \cdot 1.5 \quad M_{\mathrm{F}} = 8.622 \times 10^3 \quad \text{Lbs} \cdot \text{Ft}$$

total factored shear force at span base: $V_f := V_{\text{fact}} \cdot 1.5$	$V_f = 848.774$	lbs
---	-----------------	-----

Total factor cost Axiol: $N_{\text{tot}} = N_{\text{max}} = 2.2$ $N_{\text{f}} = 1.064 \times 10^3$ Lib

According to the analysis results from Cision's program, the foundation was found to be adequately

2. Check the supporting pipe:

The max moment on the supporting piers ($4'' \times 8$ SCH 40, $S_x = 3.21 \text{ in}^3$, $J = 35 \text{ in}^4$)

$$M_{\text{Fe}} = M_{\text{Fe,Fe}} \cdot 12 \quad M_{\text{Fe}} = 6.467 \times 10^4 \quad \text{lbs} \cdot \text{in}^3$$

$$S_{A1} = \frac{h^2_{A1}}{0.75 \times 35000} \quad S_{A1} = 2.463 \text{ in}^2 < 3.21 \text{ in}^2 \text{ Therefore, Adequate}$$

1. Wind area of the (4) HTS units: $A_1 = \frac{24 \times 71}{14} = 124$

Weight: $W_1 = 325.4$ lbs
 $W_1' = 1.3 \times 10^3$

$$M_1 = A_1 q_1 b + W_1 r_1 \frac{1}{2}$$

Find area of the distribution param:

$$A_2 = \frac{24(58 - 39.71)}{11} \cdot 1.4 \quad A_2 \approx 4.255 \quad Sq$$

Width:	$W_1 = 150$	$W_2 = 150$	lbs (Assumed)
100	100	100	100
125	125	125	125
150	150	150	150
175	175	175	175
200	200	200	200
225	225	225	225
250	250	250	250
275	275	275	275
300	300	300	300
325	325	325	325
350	350	350	350
375	375	375	375
400	400	400	400
425	425	425	425
450	450	450	450
475	475	475	475
500	500	500	500
525	525	525	525
550	550	550	550
575	575	575	575
600	600	600	600
625	625	625	625
650	650	650	650
675	675	675	675
700	700	700	700
725	725	725	725
750	750	750	750
775	775	775	775
800	800	800	800
825	825	825	825
850	850	850	850
875	875	875	875
900	900	900	900
925	925	925	925
950	950	950	950
975	975	975	975
1000	1000	1000	1000

Moment to the base:

$$M_{12} = A_2 \cdot q \cdot 5.5 - W_{12} \cdot \frac{15.75}{2}$$
$$M_{12} = -790.619 \quad \text{lb-ft}$$

3. Wind stress of the (3) Pole (4" Std Pipe, 35 Ksi Minimum strength)

type length: $\lambda_{\text{eff}} = 8$ Fl.

$$\lambda_2 = \frac{1}{12} \quad \lambda_3 = 101 \quad \lambda_4 = 1$$

Weight: $W_{ij} = (0.75, L_1)$ $W_{ij} = 254.96$ L_{1ij}

MDX: A3-Q1-2 MJJ = 806 0226 LDC = 3

$M := M_1 + M_2 + M_3$ $M = 1.578 \times 10^4$ $3 \text{ bs} = 7$

1. $\frac{1}{2} \times \frac{1}{2} = \frac{1}{4}$
 2. $\frac{1}{2} \times \frac{1}{2} = \frac{1}{4}$
 3. $\frac{1}{2} \times \frac{1}{2} = \frac{1}{4}$
 4. $\frac{1}{2} \times \frac{1}{2} = \frac{1}{4}$
 5. $\frac{1}{2} \times \frac{1}{2} = \frac{1}{4}$
 6. $\frac{1}{2} \times \frac{1}{2} = \frac{1}{4}$
 7. $\frac{1}{2} \times \frac{1}{2} = \frac{1}{4}$
 8. $\frac{1}{2} \times \frac{1}{2} = \frac{1}{4}$
 9. $\frac{1}{2} \times \frac{1}{2} = \frac{1}{4}$
 10. $\frac{1}{2} \times \frac{1}{2} = \frac{1}{4}$


4. The maximum reactions at the base of each pier

$$M_{\text{gas}} \approx 5.349 \times 10^5 \text{ } \mu\text{m} \text{--} \text{FL.}$$

$$V_{\text{max}} = A_1 q + \frac{A_2 q}{2} + A_3 q + \frac{A_4 q}{3}$$

$$V_{\text{max}} = 530.44 \quad \text{Lbs}$$


$$N_{\text{He}} = 2.2 \times 10^5 \text{ cm}^{-3}$$


[illegible][illegible]

ATC TOWER
SERVICES, INC.
8605 FREEPORT PARKWAY
SUITE 135
IRVING, TX 75063
PHONE: (972) 999-8900
FAX: (972) 999-8940
MISE INTL
ATC SITE NUMBER
308917
ATC SITE NAME
EAST
SEMIERVILLE
SITE ADDRESS
17300 GREENBERRY COURT, #200

[illegible]

H-FRAME WIND LOAD CALCULATIONS		SHEET NUMBER	REV. #
		A-3	0






NOTE:
THE FOUNDATION DESIGNS ARE BASED ON NORMAL SOILS WITH THE DESIGN PARAMETERS:
SOIL UNIT WEIGHT 100 LB/CUFT, AND COHESION $C=2000$ PSF.

SCALE NOT TO SCALE

WIRING
DIAGRAM
H-FRAME
LAYOUT

**SITE ADDRESS:**

SEVEREVALLE, JN 3/8/86

1310 J. Neurosci., July 26, 2006 • 26(30):7970–7976

APR 1964

九
香
母
木

~~CONFIDENTIAL~~


WIRING

LAYOUT


SECRETARY OF THE ARMY

1	2
---	---


1	2
---	---




1 GROUND ROD DETAIL



2 VERTICAL POST CONNECTED TO RING



3 GENERATOR GROUND RING DETAIL




4 CONDUIT TRENCH DETAIL

EQUIVALENT WIRE GROUND CABLE	
THE ELECTRICAL CONTRACTOR MAY ELECT TO USE MULTIPLE #2 THINWALL COPPER GROUND WIRES IN THIS TABLE PROVIDED THE EQUIVALENT.	
#2 AWG - 66.35 KCMIL - 0.0571 SQ. IN. - USE (1) #2G	#2 AWG - 66.35 KCMIL - 0.0571 SQ. IN. - USE (1) #2G
#4 AWG - 41.74 KCMIL - 0.0357 SQ. IN. - USE (2) #4G	#4 AWG - 41.74 KCMIL - 0.0357 SQ. IN. - USE (2) #4G
#6 AWG - 26.25 KCMIL - 0.0225 SQ. IN. - USE (3) #6G	#6 AWG - 26.25 KCMIL - 0.0225 SQ. IN. - USE (3) #6G
#8 AWG - 16.78 KCMIL - 0.0143 SQ. IN. - USE (5) #8G	#8 AWG - 16.78 KCMIL - 0.0143 SQ. IN. - USE (5) #8G
#10 AWG - 10.43 KCMIL - 0.0090 SQ. IN. - USE (8) #10G	#10 AWG - 10.43 KCMIL - 0.0090 SQ. IN. - USE (8) #10G
#12 AWG - 6.63 KCMIL - 0.0057 SQ. IN. - USE (16) #12G	#12 AWG - 6.63 KCMIL - 0.0057 SQ. IN. - USE (16) #12G

- NOTE:
1. ELECTRICAL CONTRACTOR SHALL VERIFY THAT GENERATOR IS INSTALLED SO THAT ELECTRICAL BACKFEEDS ARE NOT POSSIBLE.
 2. ELECTRICAL CONTRACTOR SHALL VERIFY THAT GROUNDING IS INSTALLED SO THAT NO GROUNDING CLIMBERS ARE POSSIBLE BY FOLLOWING GROUNDING FIELD.
 3. ALL LIGHTNING GROUNDING SHALL BE FREE OF KINKS AND SHALL HAVE LONG RADIIUS BENDS (MINIMUM 6').
 4. ALL GROUNDING SHOULD BE INSTALLED PER CURRENT NEC.
 5. USE #2 AWG SOLID THINWALL COPPER WIRE TO EXISTING [2] FENCE POSTS AND CADWELD FROM GENERATOR GROUND RING

5 H-FRAME ELEVATION




6 COMPOUND GROUNDING

SCALE
NOT TO SCALE

PROJECT NUMBER
G-1
0

COMPOUND
GROUNDING



SITE ADDRESS:
122-COUNTY CHURCH RD.
SEVIERVILLE, TN 37876

SEVIERVILLE

308917

ATC SITE NAME:
EAST

ATC TOWER
SERVICES, INC.

8605 FREEPORT PARKWAY
IRVING, TX 75039
PHONE (972) 996-8900
FAX (972) 996-9940

ATC SITE NUMBER:
308917

THIS DRAWING AND THE ACCOMPANYING SPECIFICATIONS ARE THE PROPERTY OF ATC TOWER SERVICES, INC. AND ARE NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF ATC TOWER SERVICES, INC.

ATC TOWER SERVICES, INC. IS AN EQUAL OPPORTUNITY EMPLOYER. MINORITIES AND WOMEN ARE ENCOURAGED TO APPLY.

ATC TOWER SERVICES, INC. IS AN EQUAL OPPORTUNITY EMPLOYER. MINORITIES AND WOMEN ARE ENCOURAGED TO APPLY.

ATC TOWER SERVICES, INC. IS AN EQUAL OPPORTUNITY EMPLOYER. MINORITIES AND WOMEN ARE ENCOURAGED TO APPLY.

ATC TOWER SERVICES, INC. IS AN EQUAL OPPORTUNITY EMPLOYER. MINORITIES AND WOMEN ARE ENCOURAGED TO APPLY.

ATC TOWER SERVICES, INC. IS AN EQUAL OPPORTUNITY EMPLOYER. MINORITIES AND WOMEN ARE ENCOURAGED TO APPLY.

ATC TOWER SERVICES, INC. IS AN EQUAL OPPORTUNITY EMPLOYER. MINORITIES AND WOMEN ARE ENCOURAGED TO APPLY.

ATC TOWER SERVICES, INC. IS AN EQUAL OPPORTUNITY EMPLOYER. MINORITIES AND WOMEN ARE ENCOURAGED TO APPLY.

ATC TOWER SERVICES, INC. IS AN EQUAL OPPORTUNITY EMPLOYER. MINORITIES AND WOMEN ARE ENCOURAGED TO APPLY.

ATC TOWER SERVICES, INC. IS AN EQUAL OPPORTUNITY EMPLOYER. MINORITIES AND WOMEN ARE ENCOURAGED TO APPLY.

ATC TOWER SERVICES, INC. IS AN EQUAL OPPORTUNITY EMPLOYER. MINORITIES AND WOMEN ARE ENCOURAGED TO APPLY.

GENERAC 80KW


GENERAL ASSEMBLY AND INSTALLATION SUPPLEMENT

100 - 400 Amps,
600 VAC HTS

GENERAC INDUSTRIAL

Automatic Transfer Switches

100 - 400 Amps, 600 VAC



200 Amp HTS NEMA 1

Description

- The Generac HTS Transfer Switch is a "State of the Art" Smart Switch designed to operate in conjunction with the Generac H100 Series generator controller.
- The HTS Transfer Switch has a 2 wire RS485 communication link to the generator controller.
- The utility voltage is monitored by the HTS along with signal before transfer timing, time delay neutral and inphase transfer.
- Switch operation is indicated by the generator controller.
- All timers and voltage setpoints are programmable through GenLink® Communications Software.
- Time delay neutral and inphase monitor are included.

Standard Features

- Single coil design, electrically operated and mechanically held
- Programmable exercise time
- SPDT aux contacts
- Main contacts are silver alloy
- Conformal coating protects the printed circuit board
- UL 1008 Listed
- Indicating LED's for switch position, standby operating, utility available

Optional Accessories

- NEMA 12 enclosure (100-400 Amps)
- NEMA 3R enclosure (400)

- 3 position test switch: Fast Test, Auto, Normal Test
- Arc shutes on main contacts
- Signal before transfer contacts
- Rated to all classes of loads
- Remote start, stop and transfer through GenLink® Communications Software
- Up to four transfer switches per generator
- 50/60 hertz operation
- NEMA 4 and 4x enclosure
- 4 pole for separately derived systems

100 - 400 Amps, 600 VAC

Interconnections

Switches and Indicators:

- System Ready LED
- Switch Position LED's
- Test Switch
- Return to Normal Switch
- Standby Accept Voltage
- Standby Accept Frequency
- Normal Voltage
- Allowable Deviation of Utility
- Line Interruption Delay
- Engine Warmup Time
- Minimum Run Time
- Return to Utility Timer
- Engine Shutdown Timer
- Signal before Transfer Timer
- Transfer Type
- Phase Difference for Inphase Transfer

- Standby Operating LED
- Utility Available LED
- Fast Test Switch
- Safety Disconnected Switch

HTS 100-400 Amp

Withstand Current - 600 Volt HTS Series

HTS RATED AMPS	100	150	200	300	400
FUSE PROTECTED					
Maximum RMS Symmetrical	200,000	250,000	200,000	200,000	200,000
Fault Current - Amps	200	400	400	600	600
Maximum Fuse Size - Amps	200	400	400	600	600
Fuse Class	UL	UL	UL	UL	UL
CIRCUIT BREAKER PROTECTED					
Maximum RMS Symmetrical	14,000	25,000	25,000	35,000	35,000
Fault Current - Amps	150	300	300	600	600
Protective Device Continuous Rating (Max.) - Amps	150	300	300	600	600

* Tested in accordance with the withstand and closing requirements of UL 1008 and CSA Standards.
* Current ratings are listed @ 400 VAC.


Unit Dimensions

HTS RATED AMPS	VOLTAGE	ENCLOSURE HEIGHT	ENCLOSURE WIDTH	WALL MOUNT BOLT PATTERN	ENCLOSURE DEPTH	WEIGHT (lbs.)
100	ALL	56	24	M1	OT	180
150	ALL	56	24	M1	OT	180
200	ALL	56	24	M1	OT	180
300	ALL	56	24	M1	OT	180
400	ALL	56	24	M1	OT	180

Terminal Lug Wire Ranges

HTS RATED AMPS	CONTRACTOR TERMINALS (1 LUG PER POLE)	# LUGS	NEUTRAL BAR*	GROUND LUG (1 PROVIDED)
100	20 - 14 AWG	4	20 - 14 AWG	20 - 14 AWG
150	400MCM - 4 AWG	4	350MCM - 6 AWG	350MCM - 6 AWG
200	400MCM - 4 AWG	4	350MCM - 6 AWG	350MCM - 6 AWG
300	600MCM - 4 AWG	4	600MCM - 6 AWG	600MCM - 6 AWG
400	600MCM - 4 AWG	4	1250MCM - 10 AWG	1250MCM - 10 AWG


* Not included in HTS with switched neutral. ** Allowable wire range in brackets is for 2 wires per lug.



NOTE:
1. ORIGINAL CURRENT TRANSFORMER

PART NO.	RATIO	MODEL NO.	%	VA	OHMS	"A"	"B"	"C"
0F7784A	100:1A	635-200-0-1-36	1	1	.31	.65	.28	30.5
0F7784B	200:1A	635-200-0-1-36	1	5	.95	.65	.28	30.5
0F7784C	300:1A	A-300-0-1-36	1	4.5	.06	.112	.57.1	27.4
0F7784D	400:1A	A-400-0-1-36	1	4	.11	.112	.57.1	27.4
0F7784E	500:1A	A-500-0-1-36	1	6.5	.13	.112	.57.1	27.4
0F7784F	600:1A	A-600-0-1-36	1	7.5	.15	.112	.57.1	27.4
0F7784G	800:1A	MW-800-0-1-36	1	10	.20	.143.5	.89	29.2
0F7784H	1000:1A	MW-1000-0-1-36	1	12	.22	.143.5	.89	29.2
0F7784J	1500:1A	MW-1500-0-1-36	1	15	.50	.143.5	.89	29.2
0F7784K	2000:1A	MW-2000-0-1-36	1	12	.67	.143.5	.89	29.2
0F7784L	3000:1A	MW-3000-0-1-36	1	25	1.0	.143.5	.89	29.2

2 CURRENT FLOW METER IN ATS



NOTES:
1. CONNECT TO TENANT BREAKER AT METER.
2. CONNECT TO DISTRIBUTION CENTER BRANCH BREAKER

1 ATS

GENERAC

Highway 39 & Elkhorn Rd.
Waukesha, WI 53188
Phone/262-544-4811

Ref: All Generac Power Systems fuel tank bases supplied from the factory are manufactured and labeled per U.L. 142 and are warranted through Generac Power Systems.

UL registration number: MH18459

U.L. 142 DOUBLE WALL FUEL TANK BASE SPECIFICATION

Fuel tank base construction:

- Be constructed in accordance with Underwriters Laboratories Standard U.L.-142. Be constructed in accordance with Flammable and Combustible Liquids Code, NFPA 30; The Standard for Installation and use of Stationary Combustible Engine and Gas Turbines, NFPA 37; and The Standard for Emergency and Standby Power Systems, NFPA 110. Include reinforced steel box channel for generator support, with load rating of 5,000 lbs. per gen-set mounting hole location. Full height gussets shall be provided at gen-set mounting holes. Be shipped with a certificate of Structural/Mechanical Integrity, certifying that it has met standards through rigorous testing and has demonstrated specified capabilities.

Sub Base Tank Testing:

Primary tank and secondary containment basin sections shall be pressurized at 3-5 psi and leak-checked to ensure integrity of sub base weld seams per U.L.-142 standards

Sub Base Tank Fittings:

The sub base tank shall include the following fittings:

- Appropriately sized NPT
- Fuel supply Fuel return fitting
- NPT for normal vent, sized as appropriate NPT for emergency vent, sized as appropriate
- 2" NPT for manual fill
- NPT for level gauge, sized as appropriate.
- 2" NPT for electronic fuel level; includes Low fuel alarm, High fuel level alarm
- NPT fitting for leak detection alarm

Fuel Level Gauge

The sub base tank shall include a direct-reading fuel level gauge.

Low Fuel Level

Factory Pre-set at 40% remaining for Alarm
Factory Pre-set at 20% remaining for Shut-down

High Fuel Level

Factory Pre-set at 90% full for Alarm


Fuel Containment Basin

Sub base tank shall include a welded steel containment basin, sized at a minimum of 110% of the tank capacity to prevent escape of fuel into the environment in the event of a tank rupture. A fuel containment basin leak detector switch shall be provided.

Sub Base Tank Venting

Normal and Emergency Venting:


Normal and Emergency venting shall be sized per U.L. 142 specifications for wetted surface area of tank.




NOTE: POLARIS TAP MUST BE SECURELY WRAPPED WITH COMMERCIAL GRADE NYLON ELECTRICAL TAPE AFTER INSTALLATION IS COMPLETE

NOTE: BONDING JUMPER/ GROUNDING ELECTRODE CONDUCTOR SHALL BE #4 CU FOR 200A PER NEC TABLE 250.66.

PER NEC 312.8(3), PROVIDE WARNING LABEL (PHENOLIC PLATE) ON ENCLOSURE CONTAINING POLARIS TAP SPECIFYING LOCATION OF MEANS OF DISCONNECT FOR FEEDERS BEING SPLICED.




1 MULTI-TENANT METER OPTION
SCALE: NOT TO SCALE




NOTE: POLARIS TAP MUST BE SECURELY WRAPPED WITH COMMERCIAL GRADE NYLON ELECTRICAL TAPE AFTER INSTALLATION IS COMPLETE

THE ALTERNATE NEUTRAL CONNECTION DETAIL IS INTENDED TO SHOW NEUTRAL CONNECTIONS ONLY. ALL OTHER (NON-NEUTRAL) CONNECTIONS SHOWN ON THE MULTI-TENANT METER DETAIL TO THE LEFT ARE OMITTED FOR CLARITY.



2 ALTERNATE NEUTRAL CONNECTION FOR MULTI-TENANT METER OPTION
SCALE: NOT TO SCALE



UT, ACI, MOON, CARTONS
REF # DESCRIPTION
BELL TEST _____
HI-POT _____
S/F _____

GENERAL INFORMATION

(SECTION 1 OF 1)

SERVICE VOLTAGE: 120/240V, 1PH, 3W
BUS RATING & TYPE: 800A ALUMINUM
GROUND BAR: SLO. BOTTED ALUMINUM, AL OR CU CABLE
S.C. RATING: 22K A.I.C. FULLY RATED
MAIN DRIVE TYPE: MAIN LUGS ONLY, BOTTOM CABLE ENTRY
MECHANICAL: 121 #2500 (KENT) (C/VA)
NEUTRAL TERMINALS: MECHANICAL: 121 #2500 (KENT) (C/VA)
BOOK CATALOG NO. RFG2457
FRAME: COMPLETE ENCLOSURE (INCLUDES TRIM)
SURFACE MOUNTED
BOX DIMENSIONS: 27 1/4" (699mm) H x 26 1/8" (668mm) W x 12.5" (318mm) D
MIN. CUTOFF SIZE: 12 1/2" (318mm) H x 12 1/2" (318mm) W
LEFT-5" (127mm) RIGHT-5" (127mm)
FINAL ID NAMEPLATE: [1] 800A
TYPE: PLASTIC, ADHESIVE BACKED [2] 120/240V 1PH 3W
COLOR: WHITE WITH BLACK LETTERS (3)
UL SERVICE ENTRANCE LABEL








TRIM LOCK HANDLE LOCK ASSEMBLY
CIRCUIT DIRECTOR PLASTIC SLEEVE WITH CARD
PAINTED BOX PANS 91

PLANT INFORMATION

UL LABEL:	PART NUMBER	QTY	PART NUMBER	QTY
NEUTRAL:	7499A00H01	1	EDB2200	4
GROUND BAR, AL/CU:	6622C4603	2		
CHASSIS ASSEMBLY:	6572C78603	1		
LUG ASSEMBLY:	6572C25506	1		
DRIVE ASSEMBLY:	6572C25506	1		
DEAD FRONT COVER:	5556C11801	2		
COVER PACKAGING:	4177866602	1		
DEAD FRONT COVER ASSEMBLY:	6574C74602	1		
PACKAGING:	50C3300001	1		

SPOL _____ Final Inspection _____

NOGS



SECTION A-A

SECTION B-B

DISTRIBUTION PANEL

SCALE NOT TO SCALE

DISTRIBUTION PANEL DETAILS


SCALE NOT TO SCALE

GENERAC
INDUSTRIAL

Industrial Diesel Generator Set

EPA Emissions Certification: Tier III

80 kW Diesel




Standby Power Rating
100 kVA 80 kW 60 Hz

Prime Power Rating
90 kVA 72 kW 60 Hz

features

benefits

Stereotype	
• PRODIGE ET SOCIALEMENT TESTÉ • LIÉGÉ ET CÉLÉBRE • RÉSISTANCE AU CHANGEMENT • VERTUE D'ÊTRE EN CONTACT AVEC LA NATURE	➤ PRODIGE ET SOCIALEMENT TESTÉ ➤ LIÉGÉ ET CÉLÉBRE ➤ RÉSISTANCE AU CHANGEMENT ➤ VERTUE D'ÊTRE EN CONTACT AVEC LA NATURE
Exotic	
• EN TOUTE COMPLAINT • INDIVIDUEL, TESTÉ, SOUS-ÉVALUÉ, APPROVÉ • POUVANT ÊTRE D'UNE QUALITÉ • INDIVIDUEL, ÉLÉVE	➤ EN TOUTE COMPLAINT ➤ INDIVIDUEL, TESTÉ, SOUS-ÉVALUÉ, APPROVÉ ➤ POUVANT ÊTRE D'UNE QUALITÉ ➤ INDIVIDUEL, ÉLÉVE
Alternative	
• THÉORISER AVEC • L'ART, L'ARTISANAT, LA CUISINE • L'ART ET L'ARTISANAT • DÉVELOPPER L'ARTISANAT, LA CUISINE	➤ THÉORISER AVEC ➤ L'ART, L'ARTISANAT, LA CUISINE ➤ L'ART ET L'ARTISANAT ➤ DÉVELOPPER L'ARTISANAT, LA CUISINE
Cognitive	
• ÉVALUATION D'UN PRODUIT EN BASE DE LA NATURE • L'ARTISANAT, LA CUISINE, LA CUISINE • L'ARTISANAT, LA CUISINE, LA CUISINE • L'ARTISANAT, LA CUISINE, LA CUISINE	➤ ÉVALUATION D'UN PRODUIT EN BASE DE LA NATURE ➤ L'ARTISANAT, LA CUISINE, LA CUISINE ➤ L'ARTISANAT, LA CUISINE, LA CUISINE ➤ L'ARTISANAT, LA CUISINE, LA CUISINE



primary codes and standards



SD080

ENGINE SPECIFICATIONS

[illegible]

ALTERNATOR SPECIFICATIONS

[illegible]

CODES AND STANDARDS COMPLIANCE (WHERE APPLICABLE)

NEPA 99
 NEPA 110
 ISO 8528-5
 ISO 1708A.5
 ISO 3046
 BS5514
 SAE J1349
 DIN6271
 IEEE C62.4 TESTING
 NEWMICS)

Reading Definitions
Standby - Applicable for a varying emergency load for the duration of a utility power outage with no overload capability. (Max. load factor = 70%)
Prime - Applicable for supplying power to a varying load in lieu of utility for an unlimited amount of running time. (Max. load factor = 80%)
Available for 1 out of every
 12 hours

application and engineering data

80 kW Diesel

operating data (60Hz)

.....

72	Amps	300
72	Amps	250
72	Amps	217
72	Amps	108
72	Amps	97

5KVVA v. Voltage Dip

	400/1°C					200/2°C					225/2°C						
	10%	15%	20%	30%	35%	10%	15%	20%	25%	30%	35%	10%	15%	20%	25%	30%	35%
Alternator	124	136	147	161	174	124	136	147	161	174	187	124	136	147	161	174	187
Generator	80	59	80	117	141	74	59	80	115	141	165	74	59	80	114	140	164
Upstart 1	100	79	118	157	197	126	76	125	165	215	255	100	79	118	148	177	206
Upstart 2	125	116	174	232	280	148	106	174	232	281	335	125	116	174	218	261	305

*400/1°C Alternator starts at 100°C, 200/2°C starts at 100°C, 225/2°C starts at 100°C.

Upstart 1 provides full turn of equal to class A temperature rise.

Upstart 2 provides full turn of equal to class A temperature rise.

Uspitze is provided with an equal to Class A temperature rise.

Fuel Consumption Rates

Fuel Pumping Life, in (mi)		STAINBURY		KODAK	
361.9%		gpm	lph	gpm	lph
Total Fuel Pumping Flow (Combined Return)	219%	2.1	20%	7.2	
	50%	3.5	7.0	1.5	
	4.0%	1.0	20%	4.5	
	2.0%	2.0	100%	17.5	
	100%	0.1	33.8	5.8	22.0
13.6 gpm					

^a Refer to "Emissions Data Sheets" for maximum fuel flow for EPA and SCAMCO peaking purposes.

.....

	SYNOPSIS	FINDING
Coolant Flow per Minute	37.1 (2.8)	37.1 (2.8)
Peak Injection to Coolant	6.9 (0.6)	13.7 (1.6)
Minimum Secondary Backpressure	5.1 (0.5)	6.5 (0.6)
^{15}N - H_2O Gd ratio	125(50)	124(50)

cfm (m ³ /min)	306	(A.67)
---------------------------	-----	--------

.....

EXHAUST		STANDBY		PHEM	
Exhaust Outlet Size (Open Set)	3.0"	Exhaust Flow (Rated Output)	7601.34 L	7701.34 L	7701.34 L
Maximum Backpressure (Restriction)	1.5"	Maximum Backpressure	12.54 in Hg	12.54 in Hg	12.54 in Hg
		Exhaust Temp (Inlet/Outlet)	149/113 F	149/113 F	149/113 F

	STANDARD	PRIME
Rated Engine Speed	1800	1800
Horsepower at Rated RPM**	172	172
ft/lb (N/m)	15584.4	15584.4
Prop. Speed	210	194

** Refer to "Important Data Sheet" for additional and/or revised information.
 *** Based on "Important Data Sheet" for additional and/or revised information.

... refer to Emission Data sheets for minimum gap for EPA and sound painting purposes

Disclaimer: Operational characteristics consider maximum ambient conditions. Deter factors may apply under typical use conditions. Please consult a General Power Systems Industrial Dealer for additional details. All performance ratings in accordance with ISO2004, ISO514, ISO8516 and DIN8771 standards.

standard features and options

Wayside

- Greater Vibration Isolation
- ISO Seismic Certified/Seismic Rated Vibration Isolation
- Extended Warranty
- Report boxing
- Demuxit Communications Software
- Steel Enclosure
- Aluminium Enclosure



RS-485

- [illegible]





- [illegible]

Assistant Director

- | | | | |
|-------------------------|--|-------------------------|---|
| ☐ 1 | ☐ Permanent Magnet Synchronous Motor | ☐ 6 | ☐ Battery Storage |
| ☐ 2 | ☐ Induction Motor | ☐ 7 | ☐ Other Options _____ |
| ☐ 3 | ☐ DC Brushless (if you require Overvoltage Protection) | ☐ 8 | ☐ _____ |
| ☐ 4 | ☐ DC Brushless (if you require Overvoltage Protection) | ☐ 9 | ☐ _____ |
| ☐ 5 | ☐ DC Brushless (if you require Overvoltage Protection) | | |

A technical drawing of a rectangular container or vehicle interior, oriented vertically. The drawing includes several callout labels pointing to specific parts:

- TOP DOOR**: Points to the top opening of the container.
- VENTILATING FAN**: Points to a fan located near the top door.
- 220 V A.C.**: Indicates electrical specifications near the top door area.
- WATER TANK**: Points to a tank located inside the container, below the fan.
- ALUMINUM LIFT**: Points to a lift mechanism on the right side wall.
- WHEELS**: Points to the wheels at the bottom of the container.
- WHEELS**: Another label pointing to the wheels at the bottom.
- WHEELS**: A third label pointing to the wheels at the bottom.
- WHEELS**: A fourth label pointing to the wheels at the bottom.
- WHEELS**: A fifth label pointing to the wheels at the bottom.
- WHEELS**: A sixth label pointing to the wheels at the bottom.
- WHEELS**: A seventh label pointing to the wheels at the bottom.
- WHEELS**: An eighth label pointing to the wheels at the bottom.
- WHEELS**: A ninth label pointing to the wheels at the bottom.
- WHEELS**: A tenth label pointing to the wheels at the bottom.
- WHEELS**: An eleventh label pointing to the wheels at the bottom.
- WHEELS**: A twelfth label pointing to the wheels at the bottom.
- WHEELS**: A thirteenth label pointing to the wheels at the bottom.
- WHEELS**: A fourteenth label pointing to the wheels at the bottom.
- WHEELS**: A fifteenth label pointing to the wheels at the bottom.
- WHEELS**: A sixteenth label pointing to the wheels at the bottom.
- WHEELS**: A seventeenth label pointing to the wheels at the bottom.
- WHEELS**: An eighteenth label pointing to the wheels at the bottom.
- WHEELS**: A nineteenth label pointing to the wheels at the bottom.
- WHEELS**: A twentieth label pointing to the wheels at the bottom.
- WHEELS**: A twenty-first label pointing to the wheels at the bottom.
- WHEELS**: A twenty-second label pointing to the wheels at the bottom.
- WHEELS**: A twenty-third label pointing to the wheels at the bottom.
- WHEELS**: A twenty-fourth label pointing to the wheels at the bottom.
- WHEELS**: A twenty-fifth label pointing to the wheels at the bottom.
- WHEELS**: A twenty-sixth label pointing to the wheels at the bottom.
- WHEELS**: A twenty-seventh label pointing to the wheels at the bottom.
- WHEELS**: A twenty-eighth label pointing to the wheels at the bottom.
- WHEELS**: A twenty-ninth label pointing to the wheels at the bottom.
- WHEELS**: A thirtieth label pointing to the wheels at the bottom.
- WHEELS**: A thirty-first label pointing to the wheels at the bottom.
- WHEELS**: A thirty-second label pointing to the wheels at the bottom.
- WHEELS**: A thirty-third label pointing to the wheels at the bottom.
- WHEELS**: A thirty-fourth label pointing to the wheels at the bottom.
- WHEELS**: A thirty-fifth label pointing to the wheels at the bottom.
- WHEELS**: A thirty-sixth label pointing to the wheels at the bottom.
- WHEELS**: A thirty-seventh label pointing to the wheels at the bottom.
- WHEELS**: A thirty-eighth label pointing to the wheels at the bottom.
- WHEELS**: A thirty-ninth label pointing to the wheels at the bottom.
- WHEELS**: A fortieth label pointing to the wheels at the bottom.
- WHEELS**: A forty-first label pointing to the wheels at the bottom.
- WHEELS**: A forty-second label pointing to the wheels at the bottom.
- WHEELS**: A forty-third label pointing to the wheels at the bottom.
- WHEELS**: A forty-fourth label pointing to the wheels at the bottom.
- WHEELS**: A forty-fifth label pointing to the wheels at the bottom.
- WHEELS**: A forty-sixth label pointing to the wheels at the bottom.
- WHEELS**: A forty-seventh label pointing to the wheels at the bottom.
- WHEELS**: A forty-eighth label pointing to the wheels at the bottom.
- WHEELS**: A forty-ninth label pointing to the wheels at the bottom.
- WHEELS**: A fiftieth label pointing to the wheels at the bottom.

[illegible]

SECRET DATA
APPROX. 1000 W/OUT VISIBLE FULL GROUND PICTURE AND THE



[illegible]

RECEIVED TRAINING CENTER FOR DISTILLATION
FILE 7606 BOSTON 84604

GEORGIC POWER SYSTEMS OAK THE COMPONENTS OF THIS BUILDING WERE TO SUPPLY IN CONFORMANCE AND MUST NOT BE USED FOR ANY PURPOSES OTHER THAN FOR WHICH IT IS SUPPLIED WITHOUT THE CORRECT WRITTEN CONSENT OF GEORGIC POWER SYSTEMS.

INSTALLATION DRAWING


SD80		GENERAC POWER SYSTEMS Waukesha P.O. BOX 8 WAUKESHA, WIS. 53187	
DIESEL 4.5L IVECO		FILE NAME 0H5302C-B ATC.DWG	
TURBOCHARGED & AFTERCOOLED		SCALE N/A	SIZE B
SOUND ATTENUATED ENSL, LVL 2		DATE 08/01/01	REV
W/ 300 GALLON FTB		DWG NO. 0H5302C-ATC	B



ITEM #	TANK FITTING	FUNCTION
1	3/8" NPT COUPLING	FUEL SUPPLY
2	3/8" NPT COUPLING	FUEL RETURN
3	4" NPT WELD FLANGE	EMERGENCY VENT (OUTER)
4		FUEL LEVEL
5	2" NPT WELD FLANGE	FUEL FILL
6	4" NPT WELD FLANGE	EMERGENCY VENT (INNER)
7	2" NPT WELD FLANGE	VENT
8	3/4" NPT COUPLING	DRAIN
9	Ø 22 HOLE	LEAK DETECTOR

TANK P/N	0H480805T03	0H480905T03	0H481005T03
DIM "A"	330 (13)	635 (25)	940 (37)
TOTAL TANK CAPACITY	318 (184)	734 (194)	1154 (305)
USABLE TANK CAPACITY	299 (79)	716 (189)	1134 (300)
DRY WEIGHT (EST)	237 (522)	344 (759)	445 (982)

NOTES:
 1) ALL DIMENSIONS ARE:
 LENGTH: mm (inch)
 WEIGHT: kg (lbs)
 CAPACITY: L (gall)
 2) UL #142 LISTED



DRAWING CREATED FROM PRO/ENGINEER
 3D FILE. ECO MODIFICATION TO BE
 APPLIED TO SOLID MODEL ONLY.

INSTALLATION DRAWING

GENERIC PARTS ATTACHED TO THE EQUIPMENT & THIS
 DRAWING ARE NOT TO BE USED FOR ANY OTHER
 EQUIPMENT. THE PARTS ARE THE PROPERTY OF THE
 EQUIPMENT MANUFACTURER. © GENIEC PARTS ATTACHED TO THIS



GENERIC

B-GROUP, DW TYPE 2 TANKS

ISSUE DATE:		10/02/09	
SIZE	CAGE NO	DWG NO	REV
B		0H4610A	D
SCALE	0.075	WT-RG	--
		SHEET	1 of 1

This note is for Generac H Panel + HTS installations for American Tower.


1. Unpack the monitor, the antenna, and the data / power cable. The data / power cable is black, with DB9 data connectors on two ends, and a separate pig tail with red and black wire emerging from one of the connectors, labeled OMNIMETRIX END. Make sure that all the components are in good condition, looking for shipping damage.
2. Place the antenna on the roof of the genset, and route the antenna cable through the louvers down into the area of the genset control. BE SURE to provide a drip loop lower than the monitor to keep water from running down the antenna cable into the monitor connection. If the roof is aluminum (non-magnetic), simply mount the antenna near the roof line on the steel side walls.
3. Attach the monitor to the top of the genset control enclosure, as shown.
4. Route the power pigtail with the red and black wires through the cable entry on the back of the genset control, by raising the cable through the gate.
5. Tighten the gate screws back!
6. Attach the black wire to the ground terminal, labeled 0 on the right hand end of the terminal strip inside the genset control enclosure. Attach the red wire to the Battery+ terminal on the left hand end of the terminal strip. On 12V systems, it will be labeled "15". On 24V systems, it will be labeled "220A".
7. Attach the Antenna Cable to the front of the monitor, thumb tight.
8. Plug on the data cable, labeled "OmniMetric End" to the front of the monitor. Tighten screws.
9. Plug the data cable end labeled "Generac End" onto the Generac data connector.
10. Turn on the monitor.
11. Confirm that the LEDs light up and blink. If not, check for power on the terminal strip. If, after 5 minutes, the only LED lit is the Power LED, check the antenna mount and cable connection.
12. Allow 15 minutes for the monitor to log into the network, and then call OmniMetric at the number below to confirm installation.



Antenna

Install: on or near top of genset.
OR: install on genset side.
If roof is aluminum,
Don't install!

Do not install on roof if it is not
properly sealed.
Don't install on roof if it is not
properly sealed.
Don't install on roof if it is not
properly sealed.



General Wiring Steps:

1. Install Antenna on or near roof.
2. Connect the Red and Black power wires to the Terminal Strip 183
3. Connect DB9 connector to the OMX unit.
4. Make sure it is the end marked OMNIMETRIX END !
5. Connect DB9 connector to the Generac Diagnostic Port
6. Make sure it is the end marked GENERAC END !
7. Turn on Power Switch on the OMX unit.
8. LEDs should begin to flash.
9. If not, check power connections with volt meter.
10. Wait 15 minutes for unit to make online connection.
11. Call OMX at 770-289-8812 to confirm operation.

OmniMetric LLC		
G8500 - Generac H Panel		
George P. Burdell	REV 1.0	2/29/2011
8011640180		