



Know what's below. Call before you dig.

SOURCE OF VERTICAL DATUM:

NATIONAL GEODETIC SURVEY (NGS) ONLINE POSITIONING USER SERVICE (OPUS) GPS STATIC OR GPS RAPID STATIC SURVEY SESSION DATED 10/10/15.

PK NAIL SET IN THE ASPHALT PARKING LOT OF WAL-MART PROPERTY. ELEVATION 512.93 (NAVD 88)

VICINITY MAP

- SURVEY NOTE: -

THE LAND DEPICTED HEREON IS LOCATED IN A FLOOD HAZARD ZONE 'X' AS SHOWN ON THE FLOOD INSURANCE RATE MAP COMMUNITY PANEL NO. 47037C0141G WHICH BEARS AN EFFECTIVE DATE OF

TOTAL DISTURBED AREA = $1.34 \text{ ACRES} \pm$

BASE INFORMATION WAS TAKEN FROM AN ALTA/ACSM LAND TITLE SURVEY PREPARED BY BLUE RIDGE SURVEYING INC. DATED OCTOBER 19, 2015. DEVELOPMENT MANAGEMENT GROUP, LLC SHALL NOT BE HELD RESPONSIBLE FOR THE ACCURACY AND/OR COMPLETENESS OF THAT INFORMATION SHOWN HEREON OR ANY ERRORS OR OMISSIONS RESULTING FROM SUCH.

— STORMWATER NOTE:

1. ANY EXCAVATION, FILL OR DISTURBANCE OF THE EXISTING GROUND ELEVATION MUST BE DONE IN ACCORDANCE WITH STORM WATER MANAGEMENT ORDINANCE NO. 78-840 AND APPROVED BY THE METROPOLITAN DEPARTMENT OF WATER SERVICES.

2. METRO WATER SERVICES SHALL BE PROVIDED SUFFICIENT AND UNENCUMBERED INGRESS AND EGRESS AT ALL TIMES IN ORDER TO MAINTAIN, REPAIR, REPLACE, AND INSPECT ANY STORMWATER FACILITIES WITHIN THE PROPERTY.

3. CONTRACTOR TO PROVIDE AN AREA FOR TRUCK WASH AND/OR EQUIPMENT FUELING, IF PROPOSED, IN ACCORDANCE WITH METRO CP-10 AND/OR CP-13, RESPECTIVELY. CONTRACTOR TO COORDINATE EXACT LOCATION WITH NPDES DEPARTMENT.

4. ALL EROSION CONTROL MEASURES ARE TO BE REMOVED PRIOR TO ANY AS-BUILT APPROVALS.

SITE WASTES SUCH AS DISCARDED BUILDING MATERIALS. CHEMICALS, LITTER, AND SANITARY WASTES THAT MAY CAUSE ADVERSE IMPACTS TO WATER QUALITY. THE LOCATION OF AND OR NOTES REFERRING TO SAID BMP'S SHALL BE SHOWN ON THE EPSC PLAN.

IN ACCORDANCE WITH THE METRO STORMWATER MANAGEMENT MANUAL. VOLUME 1, SECTION 3.9, AS-BUILT CERTIFICATIONS, MWS STORMWATER DIVISION MUST APPROVE THE FOLLOWING AS-BUILTS PRIOR TO ISSUANCE OF THE USE & OCCUPANCY PERMIT

- UNDERGOUND DETENTION & WATER QUALITY INFRASTRUCTURE ABOVE GROUND DETENTION & WATER QUALITY INFRASTRUCTURE
- PUBLIC STORM SEWER INFRASTRUCTURE CUT & FILL IN THE FLOODPLAIN
- SINKHOLE ALTERATIONS

THE ENGINEER SHALL CONTACT STORMWATER DEVELOPMENT REVIEW STAFF FOR SUBMITTAL REQUIREMENTS.

NOTES BY SYMBOL		
CODE	DESCRIPTION	DETAIL
EC1>	TEMPORARY CONSTRUCTION ENTRANCE - TCP-03	2/C2.2
EC2	SILT FENCE - TCP-13	1/C2.2
EC3	TREE PROTECTION FENCE	4/C2.2
EC4	INLET PROTECTION	3/C2.2
EC5	EROSION EEL	5/C2.2
(EC6)	CONCRETE WASHOUT STRUCTURE	6/C2.2

LEGEND

SILT FENCE

TREE PROTECTION FENC

EROSION EEL

- CONSTRUCTION GENERAL PERMIT — **NOTICE OF COVERAGE (NOC) CERTIFICATION**


THE PROJECT ASSOCIATED WITH THESE PLANS IS COVERED UNDER CONSTRUCTION GENERAL AS DISTURBANCE IS APPROXIMATELY $1.34\pm$ ACRES.

CIRCLE ONE: DEVELOPER - <u>PROJECT ENGINEER</u> - OTHER: <u>DAVID S. ABBEY, P.E.</u>
PLEASE ATTACH A COPY OF THE NOTICE OF COVERAGE UNDER THE CONSTRUCTION GENERAL

NOTE: A PROJECT WILL NOT BE SCHEDULED FOR A PRE-CONSTRUCTION MEETING UNTIL THE STATE CONSTRUCTION GENERAL PERMIT NOC LETTER IS SUBMITTED.



MAP: 026-00; PARCEL: 178 **ZONE: CS**



DATE: 11-25-15 DMG Project No: **EROSION & SEDIMENT** CONTROL PLAN PHASE II